



PREVAILING WINDS

1. 2" DIA. MIN. X 10' DOUGLAS FIR LODGE POLE STAKES, BOTH SIDES
2. CINCH THE ARBOR TIE OR APPROVED EQUAL
3. A SHALLOW BASIN 2" DEEP SHALL BE FORMED AROUND BALL BELOW FINISH GRADE. TREES PLANTED IN TURF AREAS SHALL NOT HAVE BASINS.
4. FINISH GRADE
5. TREES INSTALLED WITH TURF AREAS SHALL BE INSTALLED WITHIN 1/2" OF ARBOR-GARD OR APPROVED EQUAL AT BASE OF TRUNK.
6. BACKFILL IN ACCORDANCE WITH PROJECT AGRICULTURAL SUITABILITY SOILS REPORT
7. ROOTBALL

NOTES:
 1. CROWN OF ROOTBALL TO BE 1" ABOVE FINISH GRADE.
 2. FOR ADDITIONAL INFORMATION REFER TO PLANNING NOTES AND SPECIFICATIONS.

PREVAILING WINDS

1. REMOVE NURSERY STAKE AND REPLACE WITH ONE (1) 2" DIA. MIN. X 10' LODGE POLE STAKE FOR 3 GALLON, 15 GALLON & 24 BOX SIZES. PLACED ON WINDWARD SIDE OF TREE.
2. EDGE OF SLOPE BEYOND CINCH THE ARBOR TIE OR APPROVED EQUAL
3. A SHALLOW BASIN 2" DEEP SHALL BE FORMED AROUND BALL BELOW FINISH GRADE ON DOWNWARD SIDE.
4. FINISH GRADE
5. BACKFILL IN ACCORDANCE WITH PROJECT AGRICULTURAL SUITABILITY SOILS REPORT
6. PROJECT AGRICULTURAL SUITABILITY SOILS REPORT
7. ROOTBALL

NOTES:
 1. USE NURSERY STAKE FOR 1 GALLON, 2. FOR ADDITIONAL INFORMATION REFER TO PLANNING NOTES AND SPECIFICATIONS.

PLANTING PLAN NOTES

CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY TO FURNISH AND INSTALL PLANT MATERIAL, AS SHOWN ON THE DRAWINGS AND AS DESCRIBED IN THE SPECIFICATIONS. UNLESS DESIGNATED ON THE DRAWINGS OTHERWISE, STRUCTURAL IMPROVEMENTS AND HARSCOPE SHALL BE INSTALLED PRIOR TO PLANTING OPERATIONS.

ALL WORK ON THE IRRIGATION SYSTEM, INCLUDING HYDROSTATIC COVERPAGE, AND OPERATIONAL TESTS AND THE BACKFILLING AND COMPACTION OF TRENCHES SHALL BE PERFORMED PRIOR TO PLANTING OPERATIONS.

PLANT LIST ON THE DRAWINGS SHALL BE USED AS A GUIDE ONLY. CONTRACTOR SHALL TAKEOFF AND VERIFY SIZES AND QUANTITIES BY PLAN CHECK.

SAMPLES OF FERTILIZERS, ORGANIC AMENDMENT, SOIL CONDITIONERS, AND SEED SHALL BE SUBMITTED PRIOR TO INCORPORATION. CONTRACTOR SHALL FURNISH TO THE OWNER'S AUTHORIZED REPRESENTATIVE A CERTIFICATE OF COMPLIANCE FOR SUCH FURNISHED MATERIALS.

LOCATIONS OF PLANT MATERIAL SHALL BE REVIEWED ON SITE BY THE OWNER'S AUTHORIZED REPRESENTATIVE PRIOR TO INSTALLATION. AMENDMENTS, AS INDICATED IN THE SOILS REPORT SHOWN ON THE DRAWINGS, ARE BASED ON AGRICULTURAL SUITABILITY SOILS TESTS PERFORMED BY AN AGRICULTURAL SUITABILITY CONSULTANT FOR THE PURPOSES OF FINDING SOILS REPORT. CONTRACTOR SHALL ADVISE THE OWNER'S AUTHORIZED REPRESENTATIVE OF ANY CHANGES TO THE SOILS TESTS. CONTRACTOR SHALL OBTAIN AGRICULTURAL SOILS TESTING AND RECOMMENDATIONS AFTER GRADING OPERATIONS AND PRIOR TO PLANT INSTALLATION.

TREES SHALL BE PLANTED NO CLOSER THAN TEN FEET (10') FROM UTILITIES.

TREES PLANTED WITHIN FIVE FEET (5') OF HARSCOPE OR STRUCTURES SHALL BE INSTALLED BARRIER AS APPROVED BY THE OWNER'S AUTHORIZED REPRESENTATIVE.

IF DURING PLANTING OPERATIONS THERE SEEMS TO BE ANIMAL OR NO PERCOLATION IN PLANTING PITS, CONTRACTOR SHALL CEASE PLANTING OPERATIONS AND IMMEDIATELY NOTIFY THE OWNER'S AUTHORIZED REPRESENTATIVE TO DISCUSS ALTERNATIVE TO MAINTAINING POSITIVE ROOTBALL DRAINAGE MEASURES.

CONTRACTOR TO APPLY A 2" LAYER OF MULCH, AS APPLICABLE, IN ALL SHRUB AND GROUNDCOVER AREAS. CONTRACTOR TO SUBMIT SAMPLES FOR APPROVAL PRIOR TO INSTALLATION.

PLANTING LEGEND

ABBREV.	BOTANICAL NAME	COMMON NAME	SIZE	QTY
TREES				
ON CAM	CANAMOMIUM CAMPHORA	CAMPOR TREE	24" BOX STD	14
CER TEX	CERCIS TEXENSIS	OKLAHOMA REDBUD	24" BOX STD	15
LAG IND	LAGERSTROEMIA INDICA	GRAPE MYRTLE	24" BOX MULTI	15
PN PIN	PNISQAIE PINEA	ITALIAN STONE PINE	24" BOX STD	41
PIG CHI	DIWIDYEA CHINEENSIS	CHINESE FIGTASHE	24" BOX STD	78
PAR CAL	PARUS CALIFORNIANA	BRADFORD PEAR	24" BOX STD	75
BRAD ORD	BRADORDI	INTERIOR LIVE OAK	24" BOX STD	16
QUE WIS	QUERCUS WISLIZENII	CHINESE ELM	24" BOX STD	31
ULM PAR	ULMUNUS PARVIFOLI			

PLANTING LEGEND

ABBREV.	BOTANICAL NAME	COMMON NAME	SIZE	QTY
CEA JUL	CEANOTHUS CENTENNIAL	WILD LILAC	5 GAL	301
CLP LEV	X CUPRESSOCYPARIS LEYLANDII	LEVYLAND CYRESS	15 GAL	50
EYO JAP	EUYONYMUS JAPONICUS	EUYONYMUS	5 GAL	1000
LOR CHI	LOROPETULUM CHINENSIS	CHINESE FRINGE BUSH	5 GAL	281
MEU GAP	MENHLENBERGIA CAPILLARIS	PINK MUHL Y GRASS	5 GAL	841
PHO TEN	PHORUM TENAX	NEW ZEALAND FLAX	5 GAL	50
PHO FRA	PHOTINIA FRASERI	PHOTINIA	5 GAL	326
RHA IND	RHAPOLEPIS INDICA	INDIAN HAWTHORNE	5 GAL	431
VIB TIN	VIBURNUM TINUS	LAURUSTINUS	5 GAL	137

GENERAL NOTE:
 ROCK COBBLE SHALL BE PLACED TO MINIMIZE MORTAR EXPOSURE TO THE TOP SURFACE.

#3 REBAR CONTINUOUS 2' CLEAR.

MORTAR NOTES:
 -1" MAXIMUM SEPARATION BETWEEN EXPOSED ROCK SURFACES AFTER MORTAR IS APPLIED.
 -1" MIN. 1/2" MAX. BETWEEN THE TOP OF ROCK SURFACE AND TOP OF MORTAR.

GENERAL NOTE:
 ROCK COBBLE SHALL BE PLACED TO MINIMIZE MORTAR EXPOSURE TO THE TOP SURFACE.

#3 REBAR CONTINUOUS 2' CLEAR.

MORTAR NOTES:
 -1" MAXIMUM SEPARATION BETWEEN EXPOSED ROCK SURFACES AFTER MORTAR IS APPLIED.
 -1" MIN. 1/2" MAX. BETWEEN THE TOP OF ROCK SURFACE AND TOP OF MORTAR.

NOTES:
 1. ALL PLANTS SHALL BE PLANTED AT EQUAL SPACING (TRIANGULAR) UNLESS OTHERWISE INDICATED ON PLANS.
 2. AS APPROPRIATE, CENTRIE OF PLANTS SHALL BE 1/2 OF EQUAL SPACING MINIMUM FROM EDGE OF PLANNING AREA.
 3. INSET PLANTS AS REQUIRED TO MAINTAIN SPACING AT IRREGULAR EDGES.
 4. FOR ADDITIONAL INFORMATION REFER TO PLANNING NOTES AND SPECIFICATIONS.

ORDIZ MELBY ARCHITECTS, INC.
 5800 NING AVENUE SUITE 280
 BAKERSFIELD, CALIFORNIA 93309
 TELEPHONE (861) 852-6288
 FACSIMILE (861) 852-4291

BAKERSFIELD CITY SCHOOL DISTRICT
 1300 BAKER STREET
 BAKERSFIELD CALIFORNIA 93305

FOR:
 NEW MIDDLE SCHOOL
 4715 WYNDLAND ROAD
 CALIFORNIA 93306

DANNY E. ORDIZ, AIA
 WILLIAM J. MELBY, AIA
 ARCHITECT C-14,728
 REGISTERED ARCHITECTS

IDENTIFICATION STAMP
 DIVISION OF REGULATION SERVICES
 (APRIL #02-112027)
 FILE #: 15-6

AC _____ LS _____ SS _____
 DATE _____
 PIN # 43331-112

PLANTING DETAILS
 SHEET IDENTIFICATION NUMBER
L34

BAKERSFIELD CITY SCHOOL DISTRICT
 1300 BAKER STREET
 BAKERSFIELD CALIFORNIA 93305

FOR:
 NEW MIDDLE SCHOOL
 4715 WYNDLAND ROAD
 CALIFORNIA 93306

DANNY E. ORDIZ, AIA
 WILLIAM J. MELBY, AIA
 ARCHITECT C-14,728
 REGISTERED ARCHITECTS

IDENTIFICATION STAMP
 DIVISION OF REGULATION SERVICES
 (APRIL #02-112027)
 FILE #: 15-6

AC _____ LS _____ SS _____
 DATE _____
 PIN # 43331-112

PLANTING DETAILS
 SHEET IDENTIFICATION NUMBER
L34