ADMINISTRATION ROOM FINISH SCHEDULE 'A'

#	ROOM NAME	FLOOR: CONCRETE (SEALED)	FLOOR: CARPET (GLUE DOWN)	FLOOR: SHEET VINYL	FLOOR: VINYL COMPOSITION TILE	FLOOR: CERAMIC TILE (THIN SET)	FLOOR: CERAMIC TILE (MORTAR BED)	BASE: 4" RUBBER TOPSET BASE	BASE: COVED CERAMIC TILE	NW WALL: 5/8" GYPSUM BOARD	NW WALL: 5/8" TYPE "X" GYPSUM BOARD	NW WALL: CERAMIC TILE +6" OVER 5/8" MOISTURE RESIST. GYP. BD.	NW WALL: CER. TILE +6" OVER 5/8" TYPE "X" W.R. GYP. BD.	NW WALL: CASEWORK	NW WALL: ACCORDIAN FOLDING PARTITION	NE WALL: 5/8" GYPSUM BOARD	NE WALL: 5/8" TYPE "X" GYPSUM BOARD	NE WALL: CERAMIC TILE +6" OVER 5/8" MOISTURE RESIST. GYP. BD.	NE WALL: CER. TILE +6" OVER 5/8" TYPE "X" W.R. GYP. BD.	NE WALL: CASEWORK	NE WALL: ACCORDIAN FOLDING PARTITION	SE WALL: 5/8" GYPSUM BOARD	SE WALL: 5/8" TYPE "X" GYPSUM BOARD	SE WALL: CERAMIC TILE +6" OVER 5/8" MOISTURE RESIST. GYP. BD.	SE WALL: CER. TILE +6" OVER 5/8" TYPE "X" W.R. GYP. BD.	SE WALL: CASEWORK	SE WALL: ACCORDIAN FOLDING PARTITION	SW WALL: 5/8" GYPSUM BOARD	SW WALL: 5/8" TYPE "X" GYPSUM BOARD	SW WALL: CERAMIC TILE +6" OVER 5/8" MOISTURE RESIST. GYP. BD.	SW WALL: CER. TILE +6" OVER 5/8" TYPE "X" W.R. GYP. BD.	SW WALL: CASEWORK	SW WALL: ACCORDIAN FOLDING PARTITION	CEILING: 5/8" GYPSUM BOARD	CEILING: 5/8" GYPSUM BOARD (1+LAYER EA. SIDE OF C.J.)	CEILING: 2x4 SUSPENDED T-BAR CEILING	CEILING: 2x2 SUSPENDED T-BAR CEILING	CAB.: LAM. PLASTIC COUNTERTOPS / SHELVING	CAB.: LAM. PLASTIC CABINET FACES	MISC.: H.M. DOORS & FRAMES	MISC.: S.C. DOORS & H.M. FRAMES	MISC.: SOLID PLASTIC TOILET PARTITIONS	MISC.: CEILING ACCESS PANEL	MISC.: ACCORDIAN FOLDING PARTITION	MISC.: H.M. WINDOW FRAMES	NOTES	#
101	LIBRARY	F1	F1					B1			W7						W7						W7						W7	W7 *					C1		M1	M2		S3				S2			101
102	LIBRARY OFFICE		F3					B1			W7	W7 *					W7						W7						W7						C1		M1	M2		S2				S2		• TYPE "X" ADJ. TO RM'S 103 & 104	102
103	EQUIP. STORAGE		F3					B1			W7						W7						W7						W7					C2			M1	M2		S2				S2			103
104	CONFERENCE ROOM	F1						B1			W7						W7						W7						W7						C1		M1	M2		S2				S2			104
105	TEACHER WORK ROOM		F6					B2			W6						W6						W6						W6						C1		M3	M2	S3	S5							105
106	CORRIDOR		F5					B2		W6						W6	W6 *						W6	W6					W6						C1					S5				S5			106
107	BOOK SUPPLY STORAGE		F6					B2			W6						W6						W6						W6	W6 *				C4			M3	M2		S5		S17				• TYPE "X" ADJ. TO RM'S 104 & 107	107
108	MEN				F9			B4		W6	W4					W6	W4					W6	W4					W6	W6	W4	W4 *			C4					S5	S6						• TYPE "X" ADJ. TO RM'S 107	108
109	COT	F5						B2		W6						W6						W6						W6						C4					S5								109
110	WOMEN				F9			B4		B12	W4					W12	W4					W12	W4					W12		W4				C9					S5								110
111	ITINERANT SERVICES		F6					B2		W6					W6		W6				W6		W6					W6							C1		M3	M2	S3				W5				111
112	ITINERANT SERVICES		F6					B2		W6					W5		W5										W5								C1				S3				W5				112
113	ITINERANT SERVICES		F6					B2		W6						W6	W6										W5								C1				S3	S5			W5				113
114	PUBLIC RECEPTION		F6					B2		W6						W6	W6			W6		—	W6												C3		M3	M2	S3								114
115	CLERICAL OFFICE	F5						B2		W6						W6				W6		—					—					—			C3		M3	M2										115
116	CORRIDOR		F5					B2		W6					W6		W6 W6 *																		C3		M3	M2		S5				S5		• TYPE "X" ADJ. TO RM'S 119 & 120	116
117	HEALTH ROOM		F5					B2		W6						W6	W6						W6												C1		M3	M2		S5							117
118	TOILET				F9			B4		W6	W4					W6	W4						W6		W4									C4					S5								118
119	JANITOR	F12						B2		W6						W6							W6												C4			M3		S5								119
120	RECORDS		F6					B2		W6						W6							W6												C4					S5								120
121	STUDENT RECEPTION		F6					B2		W6						W6						—					—					—			C3		M3	M2	S3								121
122	CONFERENCE ROOM	F5						B2		W6						W6							W6												C1					S5				S5			122
123	OFFICE	F5						B2		W6						W6							W6												C1					S5								123
124	PRINCIPAL OFFICE	F5						B2		W6						W6							W6												C1		M3	M2		S5								124
125	VICE PRINCIPAL OFFICE	F5						B2		W6						W6							W6												C1					S5								125

CLASSROOM FINISH SCHEDULE 'D', 'E', & 'F'

	#	ROOM NAME	FLOOR: CONCRETE (SEALED)	FLOOR: CARPET (GLUE DOWN)	FLOOR: SHEET VINYL	FLOOR: VINYL COMPOSITION TILE	FLOOR: CERAMIC TILE (THIN SET)	FLOOR: CERAMIC TILE (MORTAR BED)	BASE: 4" RUBBER TOPSET BASE	BASE: COVED CERAMIC TILE	N. WALL: 5/8" GYPSUM BOARD	N. WALL: 5/8" TYPE "X" GYPSUM BOARD	N. WALL: CERAMIC TILE TO +6" OVER 5/8" MOISTURE RESISTANT GYP. BD.	N. WALL: CERAMIC TILE TO +6" OVER 5/8" TYPE "X" MOISTURE RESISTANT GYP. BD.	N. WALL: CEMENT PLASTER	N. WALL: CERAMIC TILE TO +6" OVER MORTAR BED	N. WALL: TACKABLE PANELS OVER 1/2" GYP. BD. OR STRUCTURAL PLYWOOD (SEE NOTE #3)	E. WALL: 5/8" GYPSUM BOARD	E. WALL: 5/8" TYPE "X" GYPSUM BOARD	E. WALL: CERAMIC TILE TO +6" OVER 5/8" MOISTURE RESISTANT GYP. BD.	E. WALL: CERAMIC TILE TO +6" OVER 5/8" TYPE "X" MOISTURE RESISTANT GYP. BD.	E. WALL: CEMENT PLASTER	E. WALL: CERAMIC TILE TO +6" OVER MORTAR BED	E. WALL: TACKABLE PANELS OVER 1/2" GYP. BD. OR STRUCTURAL PLYWOOD (SEE NOTE #3)	S. WALL: 5/8" GYPSUM BOARD	S. WALL: 5/8" TYPE "X" GYPSUM BOARD	S. WALL: CERAMIC TILE TO +6" OVER 5/8" MOISTURE RESISTANT GYP. BD.	S. WALL: CERAMIC TILE TO +6" OVER 5/8" TYPE "X" MOISTURE RESISTANT GYP. BD.	S. WALL: CEMENT PLASTER	S. WALL: CERAMIC TILE TO +6" OVER MORTAR BED	S. WALL: TACKABLE PANELS OVER 1/2" GYP. BD. OR STRUCTURAL PLYWOOD (SEE NOTE #3)	W. WALL: 5/8" GYPSUM BOARD	W. WALL: 5/8" TYPE "X" GYPSUM BOARD	W. WALL: CERAMIC TILE TO +6" OVER 5/8" MOISTURE RESISTANT GYP. BD.	W. WALL: CERAMIC TILE TO +6" OVER 5/8" TYPE "X" MOISTURE RESISTANT GYP. BD.	W. WALL: CEMENT PLASTER	W. WALL: CERAMIC TILE TO +6" OVER MORTAR BED	W. WALL: TACKABLE PANELS OVER 1/2" GYP. BD. OR STRUCTURAL PLYWOOD (SEE NOTE #3)	CEILING: 5/8" GYPSUM BOARD	CEILING: 5/8" TYPE "X" GYP. BD. (1 - LAYER EACH SIDE OF CEILING JOISTS)	CEILING: 2x4 SUSPENDED T-BAR	CEILING: CEMENT PLASTER	CAB.: LAM. PLASTIC COUNTERTOPS / SHELVING	CAB.: LAM. PLASTIC CABINET FACES	MISC.: H.M. DOORS & FRAMES	MISC.: S.C. DOORS & H.M. FRAMES	MISC.: SOLID PLASTIC TOILET PARTITIONS	MISC.: CEILING ACCESS PANEL	MISC.: ROOF ACCESS LADDER	MISC.: PORCELAIN ENAMEL CHALKBOARD	NOTES	#
KINDERGARTEN BUILDING 'D'	101	PLAY EQUIP. STORAGE	F12						B1			W3						W3						W3						W3						C2					S3							101
	102	KINDERGARTEN CLASSROOM		F1		F2			B1					W1		W3							W3									W1		C2		C1		M1	M2	S3	S3			S1		• GYP. BD. CEILING ADJ. TO ROOM 109	102
	103	RESTROOM					F4		B4			W4				W4					W4					W4								C2					S3						W4 - DAL #D1462: ACCENT STRIP.	103
	104	TOILET					F4		B4			W4				W4				W4						W4								C2					S3						W4 - DAL #D1462: ACCENT STRIP.	104
	105	TOILET					F4		B4			W4				W4				W4						W4								C2					S3						W4 - DAL #D1462: ACCENT STRIP.	105
	106	TOILET					F4		B4			W4				W4				W4						W4								C2					S3						W4 - DAL #D1462: ACCENT STRIP.	106
	107	TOILET					F4		B4			W4				W4				W4						W4								C2					S3						W4 - DAL #D1462: ACCENT STRIP.	107
	108	KINDERGARTEN CLASSROOM		F1		F2			B1					W1								W1	W3												C2 *	C1		M1	M2	S3	S3			S1		• GYP. BD. CEILING ADJ. TO ROOM 109	108
	109	TEACHER WORKROOM			F3				B1		W3					W3							W3												C2			M1	M2	S3		S16				109
	110	PRIMARY CLASSROOM		F1	F3				B1		W3											W1						W1	W3							C1		M1	M2	S3	S3			S1			110
INTERMEDIATE BUILDING 'E'	101	PRIMARY CLASSROOM		F1	F3				B1		W3					W3							W1						W3 *			W1			C1		M1	M2	S3	S3			S1		• TYPE "X" ADJ. TO ROOM 109	101
	102	PRIMARY CLASSROOM		F1	F3				B1		W3								W3			W1	W3												C1		M1	M2	S3	S3			S1			102
	103	PRIMARY CLASSROOM		F1	F3				B1		W3								W3			W1	W3												C1		M1	M2	S3	S3			S1			103
	104	TEACHER WORKROOM			F3				B1		W3					W3							W3												C1		M1	M2		S3							104
	105	PRIMARY CLASSROOM		F1	F3				B1					W1							W3		W3												C1		M1	M2	S3	S3			S1			105
	106	PRIMARY CLASSROOM		F1	F3				B1					W1		W3					W3											W1			C1		M1	M2	S3	S3			S1			106
	107	PRIMARY CLASSROOM		F1	F3				B1					W1		W3					W3								W3 *			W1			C1		M1	M2	S3	S3			S1		• TYPE "X" ADJ. TO ROOM 109	107
	108	GIRLS					F9		B4				W3	W4				W3	W4						W3	W4						W3	W4			C2				S3		S4				108
	109	JANITOR MECH.	F12						B1		W3					W3							W3						W3						C2			M1		S3			S3	—		109
	110	BOYS					F9		B4				W3	W4				W3	W4						W3	W4						W3	W4			C2				S3		S4				110
INTERMEDIATE/PRIMARY BUILDING 'F'	101	INTERMEDIATE CLASSROOM		F7	F8				B3		W10					W10							W9						W10 *			W9			C1		M4	M2	S7	S8			S1		• TYPE "X" ADJ. TO ROOM 109	101
	102	INTERMEDIATE CLASSROOM		F7	F8				B3		W10								W9				W9	W10												C1		M4	M2	S7	S8			S1			102
	103	INTERMEDIATE CLASSROOM		F7	F8				B3		W10								W9				W9	W10												C1		M4	M2	S7	S8			S1			103
	104	TEACHER WORKROOM			F8				B3		W10					W10					W10			W10												C1		M4	M2		S8							104
	105	INTERMEDIATE CLASSROOM		F7	F8				B3					W9							W9	W10		W10												C1		M4	M2	S7	S8			S1			105
	106	INTERMEDIATE CLASSROOM		F7	F8				B3					W9		W10						W10										W9				C1		M4	M2	S7	S8			S1			106
	107	INTERMEDIATE CLASSROOM		F7	F8				B3					W9		W10						W10							W10 *			W9			C1		M4	M2	S7	S8			S1		• TYPE "X" ADJ. TO ROOM 109	107
	108	GIRLS					F9		B4				W12	W4				W12	W4						W12	W4						W12	W4				C9			S7		S4				108
	109	JANITOR MECH.	F12						B3		W10					W10					W10								W10						C5			M4		S7			S7	—		109
	110	BOYS					F9		B4				W6	W4				W6	W4						W6	W4						W6	W4				C7			S7		S4				110

FINISH TYPES :

FLOORING :

- F1 CARPET : COLLINS & AIKMAN "GUARDIAN PLUS", 30008 - SLATE.
- F2 VINYL COMPOSITION TILE : ARMSTRONG "EXCELON", #51911 - CLASSIC WHITE, 12" x 12".
- F3 SHEET VINYL : ARMSTRONG "SUFFIELD", #86803 - SANDSTONE.
- F4 CERAMIC FLOOR TILE : DAL-TILE #DK-103, MOTTLED BLUE (1) (2"x2") WITH HYDROMENT GROUT (LATEX), COLOR : #76329 - SEABREEZE.
- F5 CARPET : COLLINS & AIKMAN "GUARDIAN PLUS", 30005 - AQUA MARINE.
- F6 SHEET VINYL : ARMSTRONG "SUFFIELD", #86807 - SLATE.
- F7 CARPET : COLLINS & AIKMAN "GUARDIAN PLUS", 30010 - BRANDY.
- F8 SHEET VINYL : ARMSTRONG "SUFFIELD", #86802 - CLAY.
- F9 CERAMIC FLOOR TILE : DAL-TILE #DK-106, MOTTLED DARK GRAY (1) (2"x2") WITH HYDROMENT GROUT (LATEX), COLOR : #361 - MISTY GREY.
- F10 VINYL COMPOSITION TILE : ARMSTRONG "EXCELON", #51908 - PEWTER 12" x 12".
- F11 SOLID SHEET VINYL : TARKETT "COLLAGE OPTIMA" #09809, WELDED SEAMS.
- F12 CONCRETE : CONCRETE FLOOR SEALER

BASE :

- B1 RUBBER TOPSET BASE : BURKE #667P, GREY DAWN, 4".
- B2 RUBBER TOPSET BASE : BURKE #664P, MIST, 4".
- B3 RUBBER TOPSET BASE : BURKE #450P, MAUVE, 4".
- B4 CERAMIC WALL TILE: SEE W4.
- B5 RUBBER TOPSET BASE : BURKE #601P, BARK, 4".
- B6 COVED SHEET VINYL: TARKETT "COLLAGE OPTIMA" #09809, WELDED SEAMS.

WALL COVERING :

- W1 VINYL TACKWALL PANELS : BF GOODRICH "KOROSEAL" HARBORWEAVE, 2118-82, PALM TINT.
- W2 PAINT : SINCLAIR CM 8460.
- W3 PAINT : SINCLAIR LINEN.
- W4 CERAMIC WALL TILE : DAL-TILE #D-100, DAL-WHITE (4 1/4"x4 1/4") WITH ACCENT STRIPE : DAL-TILE #D-1497, PLUM (4 1/4"x4 1/4") @ GIRL'S, DAL-TILE #D1462, TEAL (4 1/4"x4 1/4") @ BOY'S W/ HYDROMENT GROUT POLAR WHITE @ WALLS.
- W5 VINYL TACKWALL PANELS : BF GOODRICH "KOROSEAL" HARBORWEAVE, 2118-91, GRAY FEATHER
- W6 PAINT : SINCLAIR CM 8710.
- W7 PAINT : SINCLAIR CM 8721.
- W8 PAINT : SINCLAIR CM 8680.
- W9 VINYL TACKWALL PANELS : BF GOODRICH "KOROSEAL" HARBORWEAVE, 2118-55, EARTHENWARE.
- W10 PAINT : SINCLAIR CM 8413.
- W11 PAINT : SINCLAIR CM 8413.
- W12 PAINT : SINCLAIR CM 8406.
- W13 PROTECTIVE COATING : SANITILE #6812, POLAR WHITE.

MILLWORK :

- M1 LAMINATE PLASTIC : WILSONART GREEN GLACE, #4144-6.
- M2 LAMINATE PLASTIC : WILSONART BEIGEWOOD, #7850-13.
- M3 LAMINATE PLASTIC : WILSONART GLACIER BLUE, #020-6.
- M4 LAMINATE PLASTIC : WILSONART MOCHA GLACE, #4141-6.

CEILING :

- C1 CEILING TILE : ARMSTRONG WORLD INDUSTRIES, MINABOARD CORTEGA #769s (2'-0"x4'-0"), FLUSH LAY-IN PANEL.
- C2 PAINT : SINCLAIR LINEN.
- C3 CEILING TILE : ARMSTRONG WORLD INDUSTRIES, MINATONE CORTEGA #704s (2'-0"x2'-0"), TEGULAR LAY-IN PANEL.
- C4 PAINT : SINCLAIR CM 8710.
- C5 PAINT : SINCLAIR CM 8413.
- C6 PAINT : SINCLAIR CM 8413.
- C7 PAINT : SINCLAIR CM 8710.
- C8 PROTECTIVE COATING : SANITILE #6812, POLAR WHITE.
- C9 PAINT : SINCLAIR CM 8424.

SPECIALTIES :

- S1 LIQUID CHALKBOARDS : ALLIANCE #8402 - WHITE.
- S2 PAINT : SINCLAIR CM 8680.
- S3 PAINT : SINCLAIR CM 8460.
- S4 TOILET PARTITIONS : SANTANA PRODUCTS, BLACK PAISLEY
- S5 PAINT : SINCLAIR CM 8685.
- S6 TOILET PARTITIONS : SANTANA PRODUCTS, WHITE.
- S7 PAINT : SINCLAIR CM 8460.
- S8 PAINT : SINCLAIR CM 8406.
- S9 STAIR TREADS / SKIRTS : BURKE "MARBLE RUBBER", # 667-M, GREY DAWN.
- S10 LOCKERS : MEDART, SALMON 33.
- S11 PAINT : SINCLAIR CM 8405.
- S12 FOLDING TABLES (TOP) : FOG DUST, #1816.
- S13 FOLDING TABLES (BENCH) : BORDEAUX, #876.
- S14 FOLDING PARTITIONS : MODERNFOLD VINYL - ROSE BLUSH #16668-47.
- S15 STAGE CURTAINS : CORAL INC., COLOR: ROSE.
- S16 PAINT : SINCLAIR LINEN.
- S17 PAINT : SINCLAIR CM 8710.

MISCELLANEOUS NOTES:

1. MECHANICAL GRILLES & LOUVERS SHALL BE PAINTED TO MATCH THE IMMEDIATE ADJACENT SURFACE.
2. REFER TO FINISH SCHEDULE FOR DOOR FACE AND FRAME, PAINTS.
3. VIEW PANEL FRAMES AND LOUVERS WITHIN DOORS SHALL BE PAINTED TO MATCH THE DOOR COLOR.
4. PROVIDE HORIZONTAL MINI-BLINDS AT WINDOWS IN ROOM 112, BAND STORAGE. BLINDS SHALL BE LEVELOR #230 - PINK.
5. ALL DOOR FRAMES SHALL BE GROUTED SOLID.
6. VINYL EDGE STRIPS AND TRANSITION STRIPS SHALL BE USED WITH COVED SHEET VINYL.
7. REFER TO INTERIOR ELEVATIONS FOR CLARIFICATION OF SPECIFIC FINISH LOCATIONS AND EXTENT OF FINISHES.
8. REFER TO REFLECTED CEILING PLAN FOR CLARIFICATION OF SPECIFIC FINISH LOCATIONS AND EXTENT OF FINISHES.
9. THESE TACKABLE WALL PANELS ARE INSTALLED OVER 1/2" GYPSUM BOARD OR 1/2" STRUCTURAL SHEAR WALL PLYWOOD (WHERE INDICATED ON THE STRUCTURAL DRAWINGS). IN LOCATIONS WHERE PLYWOOD IS INSTALLED THE GYPSUM BOARD MAY BE OMITTED.

DOOR SCHEDULE

	DOOR NO.	HARDWARE	LABEL MIN	DOORS: OPENING SIZE	DOORS: TYPE	DOORS: MATERIAL	FRAMES: MATERIAL	FRAMES: WIDTH	FRAMES: HEAD DETAIL	FRAMES: JAMB DETAIL	FRAMES: SILL DETAIL	REMARKS
BUILDING 'A'	1	3		3'-0" x 7'-10"	B	HM	HM		8.1.04	8.1.04	8.1.03	
	2	4										
	3	3										
	4	5										
	5	5										
	6	5										
	7	2										
	8	2										
	9	6										
	10	3		3'-0" x 7'-10"	B	HM			8.1.04	8.1.04	8.1.03	
	11	7		3'-0" x 7'-0"	D	SC			8.1.01	8.1.01	11 A.29	
	12	8	45									
	13	9	45									
	14	10										
	15	10	45									
	16	11										SIGN 'MEN'
	17	11										SIGN 'WOMEN'
	18	12										SIGN 'WOMEN'
	19	9		3'-0" x 7'-0"	D	SC	HM		8.1.01	8.1.01		
	20	13		3'-0" x 2'-6"	G	LP	LP					
	21	14		3'-0" x 7'-0"	D	SC	HM		8.1.01	8.1.01		SIGN 'TOILET'
	22	15	45									
	23	10		3'-0" x 7'-0"	D	SC	HM		8.1.01	8.1.01		
	24	13		3'-0" x 2'-6"	G	LP	LP					
	25	16		3'-0" x 7'-0"	D	SC	HM		8.1.01	8.1.01		
	26	16			F							
	27	16										
	28	16		3'-0" x 7'-0"	F	SC	HM		8.1.01	8.1.01		
	29			3'-0" x 2'-6"	G	LP	LP				11 A.29	
BUILDING 'D'	1	18	45	3'-0" x 7'-10"	B	HM	HM		8.1.04	8.1.04	8.1.03	
	2	5			C							PANIC HARDWARE
	3	5										PANIC HARDWARE
	4	5										PANIC HARDWARE
	5	3										
	6	3										
	7	5		3'-0" x 7'-10"	C	HM			8.1.04	8.1.04	8.1.03	PANIC HARDWARE
	8	39		2'-0" x 7'-0"	D	SC			8.1.01	8.1.01	11 A.29	SIGN 'TOILET'
	9	39		3'-0" x 7'-0"								
	10	39		3'-0" x 7'-0"								
	11	7		2'-0" x 7'-0"	D							SIGN 'TOILET'
	12	40		3'-0" x 7'-0"	F							
	13	40		3'-0" x 7'-0"	F	SC	HM		8.1.01	8.1.01	11 A.29	
BUILDING 'E' & 'F'	1	5		3'-0" x 7'-10"	C	HM	HM		8.1.04	8.1.04	8.1.03	
	2	5										
	3	5										
	4	5										
	5	5										
	6	5			C							
	7	19			B							SIGN 'WOMEN'
	8	20	45		B							
	9	19		3'-0" x 7'-10"	B	HM			8.1.04	8.1.04	8.1.03	SIGN 'MEN'
	10	37		3'-0" x 7'-0"	F	SC			8.1.01	8.1.01	11 A.29	
	11	37										
	12	37										
	13	37										
	14	37										
	15	37		3'-0" x 7'-0"	F	SC	HM		8.1.01	8.1.01	11 A.29	

EXIT DOOR REQUIREMENTS

ALL EXIT DOORS IN SCHOOL BUILDING, INCLUDING BUT NOT LIMITED TO DOORS OF TOILETS AND STORAGE ROOMS, SHALL CONFORM WITH THE REQUIREMENTS OF SECTION 3304 OF THE 1988 UNIFORM BUILDING CODE WITH CALIFORNIA AMENDMENTS. THE FOLLOWING ARE SOME OF THE REQUIREMENTS:

1. EXIT DOORS SHALL BE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR ANY SPECIAL KNOWLEDGE OR EFFORT.
2. HAND ACTIVATED DOOR OPENING HARDWARE SHALL BE CENTERED BETWEEN 30 AND 44 INCHES ABOVE THE FLOOR.
3. DEAD BOLTS ARE NOT PERMITTED UNLESS OPERABLE WITH A SINGLE EFFORT BY LEVER TYPE HARDWARE.



KEY PLAN

APPROVALS

KLASSEN CORPORATION
Architecture
Planning
Construction
2021 Westwind Drive
Bakersfield, CA 93301
(805) 327-0875
(805) 327-5933 Fax

LICENSED ARCHITECT L. PAUL KLASSEN C10401 REV 1-31-95 STATE OF CALIFORNIA

The above drawings and specifications and ideas, designs and arrangements represented thereby are and shall remain the property of the architect and no part thereof shall be copied, disclosed to others or used in connection with any work or project other than the specific project for which they have been prepared and developed without the written consent of the architect. Visual contact with these drawings or specifications shall constitute conclusive evidence of acceptance of these restrictions.

Written dimensions on these drawings shall have precedence over scaled dimension. contractors shall verify and be responsible for all dimensions and conditions on the job and report any errors, omissions or conflicts to the architect. Discrepancies and conditions shown on these drawings. Shop details must be submitted to this office for approval before proceeding with fabrication.

BAKERSFIELD CITY SCHOOL DISTRICT

MESA MARIN ELEMENTARY SCHOOL

BAKERSFIELD, CA.

Sheet title: ADMINISTRATION / LIBRARY & CLASSROOMS FINISH SCHEDULES

Date:	Issued for:
12-26-92	OSA SUBMITTAL
03-11-93	OSA BACKCHECK
2-4-94	IB 12

Date:	Revisions:
10-94	A AS BUILTS

Drawn by: done

Job no: 1223

Dgn. file: mma17

Sheet: A.17

Sheet of: 31

Date: Jan 14, 1994