DEALE AVE.

KING STREET

ALLEY

EUREKA STREET

EXIST. 6" SAN. SEWER @ -6'±

SADDLE INTO 8" CITY OF BAKERSFIELD SEWER MAIN

EXIST. M.H.

EXIST. S.O.V. IN BOX

C.O.T.C.

C.W. (PVC)

E.W. (PVC)

PROVIDE 4" V.C.P. SAN. SEWER @ 1%±

EXIST. 2" WATER OF P.V.C. TO YARD SPRINKLERS, EXACT LOCATION NOT VERIFIED.

C.W. (PVC)

E.W. (PVC)

LOCKER SHELTER

EXIST. GAS METER

TEMPORARY CLASSROOMS

PROVIDE 2" GAS S.O.C. @ EXIST. HDG. PER M-1 - 6-10-69

DELETE "TIE IN" TO C.W. LINE AS INDICATED ON M-1, DATED 6-10-69 AND DELETE 2" C.W. TO NEW WING.

PROVIDE 2" C.W. PLUGGED TEE FOR FUT. USE

2"G., 2"C.W. @ -24" BELOW

3" GAS P.T. FOR FUT. USE
2" C.W. P.T. " " "
3½" C.W.
REF. M-1

ABANDONED 24"ø CONCR. DRAIN @ 22" BEL. MIN. GR.

VERIFIED 24"ø CONCR. STORM DRAIN - ABANDONED BY CITY.

T.& F. - 24"ø CONCR. @ -24" BEL. GR.

EXTEND 4" V.C. SEWER SOUTH @ 1%±

NEW CLASS ROOM WING

2" SALV. C.W. @ -18" BEL. GR.

EXIST. BUILDING

2" C.W. S.O.V. IN BOX PER M-1 - 6-10-69

2" G. PER M-1

2" GAS S.O.C. IN BOX "AS PER M-1 - 6-10-69"

REF. M-1 - 6-10-69

C.O.T.C. PER M-1

PIPE SLEEVES PER ADDENDUM NO. 1 BELOW CONCR. WALLS

DELETE SAN. SEWER INTO KING ST. PER SITE PLAN, M-2 M-1 - 6-10-69

PROVIDE 2" C.W. INTO "SCHOOL SIDE" OF METER, EXTEND SOUTH @ 18" BEL. GR. (MIN.) & RUN PARALLEL TO EXIST. W.L. (EXIST. ELECTRIC COMPACT WIRING) & MAKE EXACT CONNECTION. DO NOT CONNECT INTO "PLASTIC" EXIST. WATER METER FOR SCHOOL.

EXIST. S.O.V. AND VACUUM BREAKS FOR YARD SPRINKLERS.

DOMESTIC WATER FROM BASS AVE.

EXIST. CLASS ROOMS

EXIST. CLASS ROOMS

1" = 20'

NORTH

INSTALLATION, MATERIALS, AND PROCEDURES SHALL BE IN ACCORDANCE WITH PROJECT DOCUMENTS UNLESS NOTED OTHERWISE.

REFERENCE DRWGS: M-1 - 6-10-69
A-1 - 6-10-69

NOTES:

1. NO CITY SEWER MAIN @ "KING & EUREKA" STREETS; CLOSEST AVAILABLE TIE-IN POINT TO CITY SEWER AS NOTED.
2. PROVIDE RE-ROUTING OF DOMESTIC COLD WATER TO NEW CLASSROOM WING AND AVOID CONNECTION INTO DS "DOMESTIC USE OF PLASTIC PIPING" WATER SOURCE TO BE FROM NEAREST LOCATION @ WATER METER.
3. UTILIZE SAME PIPE TRENCH FOR NAT. GAS AND WATER.

STATE OF CALIFORNIA — DEPARTMENT OF GENERAL SERVICES
OFFICE OF ... HOUSING AND CONSTRUCTION
32138 APPROVED OCT 24 1969
APPLICATION NO. ... BY ...

CHECK AND VERIFY ALL DIMENSIONS AND CONDITIONS AT JOB SITE BEFORE PROCEEDING WITH THE WORK REPORT ANY DISCREPANCIES TO THE ARCHITECT

APPROVED BY
BOARD OF EDUCATION
BAKERSFIELD CITY SCHOOL DISTRICT
DATE OCT 13 1969
BY ...
SUPERINTENDENT OF SCHOOLS AND SECRETARY OF THE BOARD

J. W. RADEMACHER
CONSULTING ENGINEER
M.E. 11188 TA-6210
BAKERSFIELD CALIFORNIA

MARK	DATE	REVISION
1		
2		
3		
4		
5		

DRAWN J.R.
DATE 8-27-69
JOB NO. 6819A-1
CHECKED ...

EDDY AND PAYNTER
ARCHITECTS C-6921 C-11934
2901 H ST. • 323-6048
BAKERSFIELD • CALIF.

E P
A.I.A.
C-1954

CHANGE ORDER NO. 1
TO MECHANICAL SITE PLAN
LINCOLN JUNIOR HIGH SCHOOL ADDITION
BAKERSFIELD CITY SCHOOL DISTRICT
BAKERSFIELD, KERN COUNTY, CALIFORNIA

M2

OF SHEETS