9'-10 3/4"

1'-11 1/4" | 1'-11 1/4" | 2'-1 3/4" | 1'-11 1/4" | 1'-1 1/4"

4'-0" x 9'-7 3/4" x 3/4" PLYWOOD C.D. GRADE W/ EXTERIOR GLUE & STD. WD CLEATS. #10 F.H. S.T.S. @ 6" O.C. @ PERIMETER & 12" O.C. @ INTERIOR SUPP.

8'-0" | 4'-0" | 4'-0" | 4'-0" | 2'-9" | 1'-6" | 2'-9" | 8'-0"

7'-10 1/2"

8'-1 1/2"

10" x 3" x 14 GA C (TYPICAL)

2-V-DVG-1 | 2-V-DVG-1 | 2-V-DVG-1 | REF 2-V-DVG-1 | 2-V-DVG-1

1" Ø LAG BOLTS @ 15'-5 5/16"

FB3 R.H. | FB2 R.H. | FB1 R.H. | FB1 L.H. | FB2 L.H. | FB3 L.H.

FB4

N SS-1 — DETAIL 'N' @ JOINT OF MODS. ONLY

J SS-1

K SS-1

H SS-1

D SS-3

FRONT

SPACING FOR 5/8" Ø LAG BOLTS

FLOOR PLAN 3/8" = 1'-0"

1 1/2" | 3" x 3" x 3/16" TUBE | 3/4" PLYWOOD

10" x 3" C

3/16" PL TOP & BTM 2 3/4" x 6'-3"

2" x 2" x 3/16" L x 6'-1"

2" x 2" x 3/16" L x 6'-1 1/2"

COPE 10" x 2" C TOP & BTM

8 1/2 TYP

SECTION J SS-1

3/4" PLY

3/16" PL TOP & BTM

3/16" x 6" x 9'-3/16"

SECTION "1-1"

10" x 3" C

14 GA - SIM - L

8 1/2 TYP

SECTION J SS-1 2

FLG TO WALL

SECTION "2-2"

3/4" PW

3 @ 12 1/2" TYP

8" x 8" FLAT BAR

10" x 3" C

8 1/2

14" x 1" FLAT BAR

SECTION K SS-1

SECTION N SS-1 DETAIL @ JOINT OF MODS ONLY

8 1/4

8 1/2 TOP & BTM

8 1/2

SECTION "3-3"

REG'D

REGISTERED PROFESSIONAL ENGINEER — EDWARD LINDSKOG — STRUCTURAL ENGINEER — STATE OF CALIFORNIA

STRUCTURAL ENGINEER	FIRE MARSHAL	DIVISION OF ARCHITECTURE	ELECTRICAL ENGINEER	OWNER
	APPROVED STATE FIRE MARSHAL STATE OF CALIFORNIA DATE JUN 20 1966 BY	STATE OF CALIFORNIA — DEPARTMENT OF GENERAL SERVICES OFFICE OF ARCHITECTURE AND CONSTRUCTION 27755 APPROVED JUN 20 1966 APPLICATION NO. For PRINCIPAL STRUCTURAL ENGINEER		

BAKERSFIELD CITY SCHOOL DISTRICT
1300 BAKER - BAKERSFIELD, CALIF.
EDUCATIONAL CENTER

JOB NO. 753

SCALE: AS NOTED | DATE: 5-9-66 | FOR 32'-0" UNIT | DRAWN BY: T. HOVILLIS | REVISED

MOBILE RENTALS CORPORATION
3240 NORTH DURFEE AVE. EL MONTE, CALIF.

SECTIONAL DETAILS & FLOOR PLAN

DRAWING NUMBER S-1

11X24 PRINTED ON NO. 1000H CLEARPRINT