



Bakersfield City School District

Maintenance, Operations and Facilities Department

1501 Feliz Drive
Bakersfield, California 93307
Office (661) 631-5883 Fax (661) 834-9986

Jason Sitton, Director I sittonj@bcسد.com
Leonard Zasoski, Assistant Director II zasoskil@bcسد.com
Daniel Wastafarro, Assistant Director II wastafarro@bcسد.com
Juan Montelongo, Assistant Director II montelongoj@bcسد.com

April 17, 2024

To: All Bidders
Re: Rafer Johnson - Asphalt Replacement Project – Addendum No. 2 (Plans, Alternates for Fencing & Asphalt Bid Packages, Revised Schedule)

1. Remove and replace original bid form due to added alternates.
2. Bids to be awarded on the base bid only.
3. All Bid Packages – Plans (Sheets 1-3) Dated 4/15/2024.
4. Bid date change. **New bid date Tuesday April 30th at 2:00pm.**
5. **Last day for questions is Wednesday April 24th.**
6. Sawcut pavement as close as possible where pavement runs under existing modular classrooms and ramps.
7. Concrete curb at the chain link fence as noted on Addendum 2 Attachment A is now part of Bid Package 01. Bid Package 01 and 02 to coordinate installation of the concrete curb and the fence post.
8. See revised project schedule attachment B.
9. Alternate for Bid Package 01 Paving to be sawcut along existing fencing see Addendum 2 Attachment A.
10. Alternate for Bid Package 02 fencing to remain on the south & east sides no temporary fencing required see Addendum 2 Attachment A.

Please date, sign and return this form via email to Brenda Orozco at orozcob@bcسد.com.


Date Print Name Signature

Print Company Name


Sincerely,

Leonard Zasoski
Assistant Director II
Maintenance, Operations and Facilities
Bakersfield City School District

"N" STREET



SEE SHEET 3



TOPO LEGEND

- (A) AC UNIT
- (B) SEWER CLEANOUT OR BOX
- (C) FLAG POLE
- (D) CONCRETE CURB
- (E) WATER VALVE
- (F) WATER METER BOX/VAULT
- (G) IRRIGATION BOX
- (H) ELECTRICAL GROUND
- (I) CONCRETE PAD/STOOP
- (J) LIGHT STANDARD
- (K) RAMP LANDING
- (L) PIPE OR CONDUIT
- (M) WATER SPOUT
- (N) UTILITY ENCLOSURE
- (O) TRUNCATED DOMES
- (P) CONCRETE AREA
- (Q) STAINLESS STEEL PEDESTAL
- (R) DRINKING FOUNTAIN
- (S) UTILITY BOX

CONSTRUCTION NOTES

- 1. REMOVE EXISTING PAVEMENT AND CONSTRUCT 0.25' MIN. ASPHALT PAVEMENT OVER 0.40' MIN. CLASS II AGGREGATE BASE OVER 1.0' MIN. NAT. GRD. COMPACTED TO 95% MAX DENSITY. FINISHED ASPHALT PAVEMENT GRADE TO BE PLACED AT DESIGN ELEVATIONS SHOWN.
- 2. REMOVE EXISTING PAVEMENT AND CONSTRUCT 0.25' MIN. ASPHALT PAVEMENT OVER 0.40' MIN. CLASS II AGGREGATE BASE OVER 1.0' MIN. NAT. GRD. COMPACTED TO 95% MAX DENSITY. FINISHED ASPHALT PAVEMENT GRADE TO BE PLACED AT SAME ELEVATION AS EXISTING.
- 3. CONSTRUCT 2' WIDE V-GUTTER PER DETAIL (B/T).
- 4. CONSTRUCT FLUSH CURB PER DETAIL (A/T).
- 5. FLARE GUTTER DEPRESSION.
- 6. COORDINATE REMOVAL AND RE-INSTALLATION OF RAMP WITH DISTRICT.
- 7. PROTECT EXISTING UTILITY IN PLACE. ADJUST TO GRADE.
- 8. PROTECT EXISTING STRUCTURE IN PLACE.

NOTES:

1. ACCESSIBLE PARKING SHALL NOT EXCEED 2% MAXIMUM SLOPE IN ANY DIRECTION. CONTRACTOR SHALL PROTECT ALL EXISTING IMPROVEMENTS, UNDERGROUND UTILITIES, ETC. TO REMAIN IN PLACE AND SHALL REPAIR ANY DAMAGES DURING CONSTRUCTION ACTIVITIES.
2. EXISTING UNDERGROUND UTILITIES HAVE BEEN SHOWN BASED ON AVAILABLE RECORDS. CONTRACTOR SHALL VERIFY LOCATION AND DEPTHS OF UTILITIES PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER OF ANY CONFLICTS.
3. ADD 400' TO ALL DESIGN GRADES.


LEGEND

- DESIGN GRADE
- DESIGN SLOPE
- EXISTING GROUND CONTOUR
- EXISTING GRADE
- MATCH EXISTING ELEVATION
- EX. WROUGHT IRON FENCE
- EX. CHAIN-LINK FENCE
- EX. EDGE OF PAVING

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THE ENGINEER. NO PART THEREOF SHALL BE COPIED, REPRODUCED, OR USED IN CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THAT SPECIFICALLY PROVIDED FOR IN THE CONTRACT. ANY REVISIONS TO THESE DRAWINGS SHALL BE MADE BY THE ENGINEER AND SHALL BE INDICATED BY A CIRCLED NUMBER AND A LETTER. THE WRITTEN CONSENT OF THE ENGINEER IS REQUIRED FOR ANY REVISIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR THE ACCURACY OF ALL DIMENSIONS AND CONDITIONS SHOWN ON THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

PORTER & ASSOCIATES, INC.
ENGINEERING & SURVEYING
1707 Eye Street, Suite 111
Bakersfield, California 93301
661.327.0362

FRED W. PORTER II
PROJECT ENGINEER: 000.000
DRAFTSMAN: LOH
PA REVIEW BY: _____
DATE: _____



**PAVEMENT REPLACEMENT PLAN
RAFER JOHNSON SCHOOL
BAKERSFIELD CITY SCHOOL DISTRICT
NORTH PORTION**


REVISIONS

NO.	DESCRIPTION	DATE

DATE 04/15/2024
PA JOB No. 3324

J:\3324\Basemap (wgs) 3324_BM.dwg 04/15/24 matthewcorson


"N" STREET



THE ABOVE DRAWINGS AND SPECIFICATIONS AND DETAILS, DESIGNS, AND DIMENSIONS ARE REPRESENTED AS THE PROPERTY OF PORTER & ASSOCIATES, INC. AND SHALL REMAIN THE PROPERTY OF THE ENGINEER. NO PART THEREOF SHALL BE COPIED, REPRODUCED, OR USED IN CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THAT SPECIFICALLY AUTHORIZED BY PORTER & ASSOCIATES, INC. WITHOUT THE WRITTEN CONSENT OF PORTER & ASSOCIATES, INC. CONTRACTORS SHALL VERIFY ALL DIMENSIONS AND CONDITIONS SHOWN ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN ON THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

PORTER & ASSOCIATES, INC.
 ENGINEERING & SURVEYING
 1707 Eye Street, Suite 111
 Bakersfield, California 93301
 661.327.0362

FRED W. PORTER II
 PROJECT ENGINEER: 000.000
 DRAFTSMAN: LOH
 PA REVIEW BY: _____
 DATE: _____



PAVEMENT REPLACEMENT PLAN
RAFER JOHNSON SCHOOL DISTRICT
BAKERSFIELD CITY SCHOOL DISTRICT
SOUTH PORTION

- TOPO LEGEND**
- (A) AC UNIT
 - (B) SEWER CLEANOUT OR BOX
 - (C) FLAG POLE
 - (D) CONCRETE CURB
 - (E) WATER VALVE
 - (F) WATER METER BOX/VAULT
 - (G) IRRIGATION BOX
 - (H) ELECTRICAL GROUND
 - (I) CONCRETE PAD/STOOP
 - (J) LIGHT STANDARD
 - (K) RAMP LANDING
 - (L) PIPE OR CONDUIT
 - (M) WATER SPIGOT
 - (N) UTILITY ENCLOSURE
 - (O) TRUNCATED DOMES
 - (P) CONCRETE AREA
 - (Q) STAINLESS STEEL PEDESTAL
 - (R) DRINKING FOUNTAIN
 - (S) UTILITY BOX

- CONSTRUCTION NOTES**
- [1] REMOVE EXISTING PAVEMENT AND CONSTRUCT 0.25' MIN. ASPHALT PAVEMENT OVER 0.40' MIN. CLASS II AGGREGATE BASE OVER 1.0' MIN. NAT. GRD. COMPACTED TO 95% MAX DENSITY. FINISHED ASPHALT PAVEMENT GRADE TO BE PLACED AT DESIGN ELEVATIONS SHOWN.
 - [2] REMOVE EXISTING PAVEMENT AND CONSTRUCT 0.25' MIN. ASPHALT PAVEMENT OVER 0.40' MIN. CLASS II AGGREGATE BASE OVER 1.0' MIN. NAT. GRD. COMPACTED TO 95% MAX DENSITY. FINISHED ASPHALT PAVEMENT GRADE TO BE PLACED AT SAME ELEVATION AS EXISTING.
 - [3] CONSTRUCT 2' WIDE V-GUTTER PER DETAIL (B).
 - [4] CONSTRUCT FLUSH CURB PER DETAIL (A).
 - [5] FLARE GUTTER DEPRESSION.
 - [6] COORDINATE REMOVAL AND RE-INSTALLATION OF RAMP WITH DISTRICT.
 - [7] PROTECT EXISTING UTILITY IN PLACE, ADJUST TO GRADE.
 - [8] PROTECT EXISTING STRUCTURE IN PLACE.

- NOTES:**
1. ACCESSIBLE PARKING SHALL NOT EXCEED 2% MAXIMUM SLOPE IN ANY DIRECTION.
 2. CONTRACTOR SHALL PROTECT ALL EXISTING IMPROVEMENTS, UNDERGROUND UTILITIES, ETC. TO REMAIN IN PLACE AND SHALL REPAIR ANY DAMAGES DURING CONSTRUCTION ACTIVITIES.
 3. EXISTING UNDERGROUND UTILITIES HAVE BEEN SHOWN BASED ON AVAILABLE RECORDS. CONTRACTOR SHALL VERIFY LOCATION AND DEPTHS OF UTILITIES PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER OF ANY CONFLICTS.
 4. ADD 400' TO ALL DESIGN GRADES.

- LEGEND**
- DESIGN GRADE
 - DESIGN SLOPE
 - EXISTING GROUND CONTOUR
 - EXISTING GRADE
 - MATCH EXISTING ELEVATION
 - EX. WROUGHT IRON FENCE
 - EX. CHAIN-LINK FENCE
 - EX. EDGE OF PAVING

REVISIONS

DATE	04/15/2024
PA JOB No.	3324
SHEET	3
OF 3 SHEETS	

J:\3324\Basemap (wp)\3324_BM.dwg 04/15/24 matthewcorson

Demo existing chain link fence & gates by demo contractor BP-01
New 4' high fence & gates with slats by chain link fence contractor BP-02

Base Bid-
Demo 8' x 48 existing chain link fence & gates by demo contractor. BP-01
New fence & gates to be climb resistance fabric by BP-02
Concrete Curb to be 12" wide x 7" tall flush with the pavement by BP-01


Alternate 1-
Fencing to remain. BP-02
Saw-cut paving 6' from existing fencing by BP-01

Fencing contractor to remove existing fence fabric, gates 163' and store for re-installation. BP-02
Fence poles to be removed by the demo contractor. BP-01
New poles and stored fence fabric to be installed by BP-02

8' x 29' Fence and gates to be removed by demo contractor. BP-01
New fence and gates to be installed by fencing contractor. Fence & gates to be climb resistance fabric. BP-02

Base Bid-
Fencing contractor to install temporary fencing that will remain in place until the fence fabric is re-installed. BP-02
Fencing contractor to remove existing fence fabric, gates 320' and store for re-installation. BP-02
Fence poles to be removed by the demo contractor. BP-01
New fence poles and re installation of the fence fabric by BP-02.
Concrete curb to be 12" wide x 7" tall flush with the sidewalk by BP-01

Alternate 1-
Fencing to remain. BP-02
Saw-cut paving 6' from existing fencing. BP-01





Activity ID	Act. Assignment	Activity Name	Original Duration	Start	Finish	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J
2024 Deferred Projects						14-Aug-24, 2024 Deferred Projects																																				
Asphalt Projects						14-Aug-24, Asphalt Projects																																				
EISSLER - AC Paving Project (AC Paving, Chain Link Fence, Play Equipment)						31-Jul-24, EISSLER - AC Paving Project (AC Paving, Chain Link Fence, Play Equipment)																																				
Construction Activities						14-Aug-24, Construction Activities																																				
HORACE MANN - AC Paving Project (AC Paving, AC Slurry, Chain Link Fence)						14-Aug-24, HORACE MANN - AC Paving Project (AC Paving, AC Slurry, Chain Link Fence)																																				
LONGFELLOW - AC Paving Project (AC Paving, Chain Link Fence, Play Equipment)						14-Aug-24, LONGFELLOW - AC Paving Project (AC Paving, Chain Link Fence, Play Equipment)																																				
RAFER JOHNSON - AC Paving Project (AC Paving, Chain Link Fence, Play Equipment)						14-Aug-24, RAFER JOHNSON - AC Paving Project (AC Paving, Chain Link Fence, Play Equipment)																																				
Pre-Construction Activities						05-Aug-24, Pre-Construction Activities																																				
RJPC1000	BCSD	Create Bid Scope / RFQ	36	15-Jan-24	04-Mar-24	Create Bid Scope / RFQ																																				
RJPC1010	BCSD	Advertise Project	11	05-Mar-24	19-Mar-24	Advertise Project																																				
RJPC1020	Contractors	Bid Project	40	05-Mar-24	29-Apr-24	Bid Project																																				
RJPC1030	Contractors	Mandatory Job Walk (3:30pm)	1	13-Mar-24	13-Mar-24	Mandatory Job Walk (3:30pm)																																				
RJPC1040	Contractors	Bids Due	1	30-Apr-24	30-Apr-24	Bids Due																																				
RJPC1050	BCSD	Review Bids	1	01-May-24	01-May-24	Review Bids																																				
RJPC1110	BCSD	Notice of Intent to Award	1	02-May-24	02-May-24	Notice of Intent to Award																																				
RJPC1060	BCSD	Submit Bids to Board Docs	1	15-May-24	15-May-24	Submit Bids to Board Docs																																				
RJPC1070	BCSD	Board Awards Bids	1	28-May-24	28-May-24	Board Awards Bids																																				
RJPC1090	BCSD	Notice to Award	1	29-May-24	29-May-24	Notice to Award																																				
RJPC1080	Contractors	Contracts & Insurance	10	30-May-24	12-Jun-24	Contracts & Insurance																																				
RJPC1100	BCSD	San Joaquin Valley Air Pollution Control District - Construction Notification	3	30-May-24	03-Jun-24	San Joaquin Valley Air Pollution Control District - Construction Notification																																				
RJPC1120	BCSD	Notice to Proceed	1	12-Jun-24	12-Jun-24	Notice to Proceed																																				
Onsite Pre-Construction Activities						06-Jun-24, Onsite Pre-Construction Activities																																				
RJOPC-1000	Contractors	Underground Service Alert (USA)	3	30-May-24*	03-Jun-24	Underground Service Alert (USA)																																				
RJOPC-1020	BCSD	Site Staff Notification of Upcoming Project	1	30-May-24*	30-May-24	Site Staff Notification of Upcoming Project																																				
RJOPC-1010	BCSD	Confirm Use of Existing Restrooms	1	31-May-24*	31-May-24	Confirm Use of Existing Restrooms																																				
RJOPC-1030	Contractors	Pre-Construction Meeting (2:30pm)	1	06-Jun-24*	06-Jun-24	Pre-Construction Meeting (2:30pm)																																				
Submittals						05-Aug-24, Submittals																																				
Concrete						27-Jun-24, Concrete																																				
RJC-1000	Bid Pack 01	Site Concrete - Mix Design / Reinforcing Steel / Cure (Contractor Prepare Submittal)	10	30-May-24	12-Jun-24	Site Concrete - Mix Design / Reinforcing Steel / Cure (Contractor Prepare Submittal)																																				
RJC-1010	BCSD	Site Concrete - Mix Design / Reinforcing Steel / Cure (BCSD Review Submittal)	2	13-Jun-24	14-Jun-24	Site Concrete - Mix Design / Reinforcing Steel / Cure (BCSD Review Submittal)																																				
RJC-1020	Bid Pack 01	Site Concrete - Mix Design / Reinforcing Steel / Cure (Procurement)	2	26-Jun-24	27-Jun-24	Site Concrete - Mix Design / Reinforcing Steel / Cure (Procurement)																																				
AC Paving						25-Jul-24, AC Paving																																				
RJAP-1000	Bid Pack 01	AC Paving - Paving Material / AG Base Material (Contractor Prepare Submittal)	10	30-May-24	12-Jun-24	AC Paving - Paving Material / AG Base Material (Contractor Prepare Submittal)																																				
RJAP-1010	BCSD	AC Paving - Paving Material / AG Base Material (BCSD Review Submittal)	2	13-Jun-24	14-Jun-24	AC Paving - Paving Material / AG Base Material (BCSD Review Submittal)																																				
RJAP-1020	Bid Pack 01	AC Paving - Paving Material / AG Base Material (Procurement)	5	19-Jul-24	25-Jul-24	AC Paving - Paving Material / AG Base Material (Procurement)																																				
Striping						05-Aug-24, Striping																																				
RJS-1000	Bid Pack 01	Striping Product (Contractor Prepare Submittal)	5	30-May-24	05-Jun-24	Striping Product (Contractor Prepare Submittal)																																				
RJS-1010	BCSD	Striping Product (BCSD Review Submittal)	2	06-Jun-24	07-Jun-24	Striping Product (BCSD Review Submittal)																																				
RJS-1020	Bid Pack 01	Striping Product (Procurement)	5	30-Jul-24	05-Aug-24	Striping Product (Procurement)																																				
Construction Activities						14-Aug-24, Construction Activities																																				
Playfield On-Campus Activities						14-Aug-24, Playfield On-Campus Activities																																				
RJCA-1010	General	Start Construction	0	13-Jun-24		Start Construction																																				
RJCA-1020	Bid Pack 01	Demo Asphalt / Play Equipment / Benches Etc. @ Playfield	8	13-Jun-24	24-Jun-24	Demo Asphalt / Play Equipment / Benches Etc. @ Playfield																																				
RJCA-1030	Bid Pack 03	Rough Grading for Concrete Curb @ Playfield & Perimeter Fence	3	25-Jun-24	27-Jun-24	Rough Grading for Concrete Curb @ Playfield & Perimeter Fence																																				

█ Actual Work
 █ Critical Remaining Work
 Summary
█ Remaining Work
 ◆ Milestone

Date	Revision	Checked	Approved
17-Apr-24	Rafer Asphalt Project (Addendum 1 - Attachment B)		



Activity ID	Act. Assignment	Activity Name	Original Duration	Start	Finish	Gantt Chart (J F M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D J)																							
RJCA-1040	BCSD	Install Irrigation Sleeves @ Playfield	2	25-Jun-24	26-Jun-24	█ Install Irrigation Sleeves @ Playfield																							
RJCA-1050	Bid Pack 01	Concrete Curb @ Playfield, Form, Reinforcing Steel, Pour, Strip	6	28-Jun-24	08-Jul-24	█ Concrete Curb @ Playfield, Form, Reinforcing Steel, Pour, Strip																							
RJCA-1060	Bid Pack 01	Rough Grading @ Playfield	8	09-Jul-24	18-Jul-24	█ Rough Grading @ Playfield																							
RJCA-1160	Bid Pack 01	Concrete Curbs @ Perimeter Fence	3	15-Jul-24	17-Jul-24	█ Concrete Curbs @ Perimeter Fence																							
RJCA-1070	Bid Pack 01	Install AG Base & Compact	5	19-Jul-24	25-Jul-24	█ Install AG Base & Compact																							
RJCA-1080	Bid Pack 01	Install AC Paving	4	26-Jul-24	31-Jul-24	█ Install AC Paving																							
RJCA-1090	Bid Pack 01	Fog Seal / Paving Cure Time	1	01-Aug-24	01-Aug-24	█ Fog Seal / Paving Cure Time																							
RJCA-1100	Play Equip Conc	Install Play Equipment Poles	4	02-Aug-24	07-Aug-24	█ Install Play Equipment Poles																							
RJCA-1110	Bid Pack 01	Stripe Track & Play Courts	4	06-Aug-24	09-Aug-24	█ Stripe Track & Play Courts																							
RJCA-1150	BCSD	Install Basketball Backboards	2	08-Aug-24	09-Aug-24	█ Install Basketball Backboards																							
RJCA-1120	General	Project Complete	0		09-Aug-24	◆ Project Complete																							
RJCA-1130	BCSD	Teacher Back on Site	0	12-Aug-24*		◆ Teacher Back on Site																							
RJCA-1140	BCSD	Students Back in School	0	14-Aug-24*		◆ Students Back in School																							
Chain Link Fence			42	13-Jun-24	09-Aug-24	▼ 09-Aug-24, Chain Link Fence																							
RJCL-1000	General	Start Chain Link Fence	0	13-Jun-24		◆ Start Chain Link Fence																							
RJCL-1010	Bid Pack 02	Remove & Store Existing Chain Link Fence Fabric @ Playfield	2	13-Jun-24	14-Jun-24	█ Remove & Store Existing Chain Link Fence Fabric @ Playfield																							
RJCL-1030	Bid Pack 02	Remove & Store Existing Chain Link Fence Fabric @ Site Perimeter Fence West & South	3	13-Jun-24	17-Jun-24	█ Remove & Store Existing Chain Link Fence Fabric @ Site Perimeter Fence West & South																							
RJCL-1090	Bid Pack 02	Install Temporary Fence @ Perimeter Fence Removal	2	13-Jun-24	14-Jun-24	█ Install Temporary Fence @ Perimeter Fence Removal																							
RJCL-1020	Bid Pack 02	Demo Existing Chain Link Fence @ HVAC Equipment	3	17-Jun-24	19-Jun-24	█ Demo Existing Chain Link Fence @ HVAC Equipment																							
RJCL-1050	Bid Pack 02	Install Fence Post @ Perimeter Fence South, West & North	4	09-Jul-24	12-Jul-24	█ Install Fence Post @ Perimeter Fence South, West & North																							
RJCL-1070	Bid Pack 02	Install Perimeter Fence Fabric	3	01-Aug-24	05-Aug-24	█ Install Perimeter Fence Fabric																							
RJCL-1040	Bid Pack 02	Install Chain Link Fence Post	3	06-Aug-24	08-Aug-24	█ Install Chain Link Fence Post																							
RJCL-1060	Bid Pack 02	Install Chain Link Fabric @ HVAC & Stored Fabric @ Playfield	4	06-Aug-24	09-Aug-24	█ Install Chain Link Fabric @ HVAC & Stored Fabric @ Playfield																							
RJCL-1080	Bid Pack 02	Remove Temporary Fence	1	06-Aug-24	06-Aug-24	█ Remove Temporary Fence																							
Asphalt Slurry Projects			104	11-Mar-24	01-Aug-24	█ Asphalt Slurry Projects																							
Washington Middle School			150	15-Jan-24	14-Aug-24	█ Washington Middle School																							
McKinley Projects			152	15-Jan-24	14-Aug-24	█ McKinley Projects																							
Cato - Sport Court Restripe			89	01-Apr-24	05-Aug-24	█ Cato - Sport Court Restripe																							
Emerson Projects			69	18-Mar-24	21-Jun-24	█ Emerson Projects																							
Fall Material @ Elementary Playgrounds			121	19-Feb-24	07-Aug-24	█ Fall Material @ Elementary Playgrounds																							
Fall Mats @ Elementary Playgrounds			94	04-Mar-24	15-Jul-24	█ Fall Mats @ Elementary Playgrounds																							
Site Sweeping			82	15-Apr-24	08-Aug-24	█ Site Sweeping																							

█ Actual Work
 █ Critical Remaining Work
 ▼ Summary
█ Remaining Work
 ◆ Milestone

Date	Revision	Checked	Approved
17-Apr-24	Rafer Asphalt Project (Addendum 1 - Attachment B)		

BID FORM AND PROPOSAL

To: Governing Board of the Bakersfield City School District ("District" or "Owner")

From: _____
(Proper Name of Bidder)

The undersigned declares that Bidder has read and understands the Contract Documents, including, without limitation, the Notice to Bidders and the Instructions to Bidders, and agrees and proposes to furnish all necessary labor, materials, and equipment to perform and furnish all work in accordance with the terms and conditions of the Contract Documents, including, without limitation, the Drawings and Specifications of Bid No. 24219.00-45-DM, for the following project known as:

Rafer Johnson School Asphalt Replacement, Fencing & Install of Basketball & Tetherball Poles

("Project" or "Contract") and will accept in full payment for that Work the following total lump sum amount, all taxes included:

_____ dollars \$ _____
<i>BASE BID – Bid Package No. 01</i>

Additive/Deductive Alternates:

Alternate #1 – Asphalt Paving Changes per Addendum No. 02 Attachment A

_____ dollars \$ _____
Additive/Deductive

_____ dollars \$ _____
<i>BASE BID – Bid Package No. 02</i>

Additive/Deductive Alternates:

Alternate #1 – Fencing Changes per Addendum No. 02 Attachment A

	dollars	\$ _____
Additive/Deductive		

Descriptions of alternates are primarily scope definitions and do not necessarily detail the full range of materials and processes needed to complete the construction.

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

Additional Detail Regarding Calculation of Base Bid

1. The undersigned has reviewed the Work outlined in the Contract Documents and fully understands the scope of Work required in this Proposal, understands the construction and project management function(s) is described in the Contract Documents, and that each Bidder who is awarded a contract shall be in fact a prime contractor, not a subcontractor, to the District, and agrees that its Proposal, if accepted by the District, will be the basis for the Bidder to enter into a contract with the District in accordance with the intent of the Contract Documents.
2. The undersigned has notified the District in writing of any discrepancies or omissions or of any doubt, questions, or ambiguities about the meaning of any of the Contract Documents, and has contacted the Construction Manager before bid date to verify the issuance of any clarifying Addenda.
3. The undersigned agrees to commence work under this Contract on the date established in the Contract Documents and to complete all work within the time specified in the Contract Documents.
4. The liquidated damages clause of the General Conditions and Agreement is hereby acknowledged.
5. It is understood that the District reserves the right to reject this bid and that the bid shall remain open to acceptance and is irrevocable for a period of ninety (90) days.
6. The following documents are attached hereto:
 - Bid Bond on the District's form or other security
 - Designated Subcontractors List
 - Site Visit Certification (mandatory for BP-01, BP-02, BP-03)
 - Non-Collusion Declaration
7. Receipt and acceptance of the following Addenda is hereby acknowledged:

No. _____, Dated _____	No. _____, Dated _____
No. _____, Dated _____	No. _____, Dated _____
No. _____, Dated _____	No. _____, Dated _____

8. Bidder acknowledges that the license required for performance of the Work is a _____ license.
9. Bidder hereby certifies that Bidder is able to furnish labor that can work in harmony with all other elements of labor employed or to be employed on the Work.
10. Bidder specifically acknowledges and understands that if it is awarded the Contract, that it shall perform the Work of the Project while complying with all requirements of the Department of Industrial Relations.

11. Bidder hereby certifies that its bid includes sufficient funds to permit Bidder to comply with all local, state or federal labor laws or regulations during the Project, including payment of prevailing wage, and that Bidder will comply with the provisions of Labor Code section 2810(d) if awarded the Contract
12. Bidder represents that it is competent, knowledgeable, and has special skills with respect to the nature, extent, and inherent conditions of the Work to be performed. Bidder further acknowledges that there are certain peculiar and inherent conditions existent in the construction of the Work that may create, during the Work, unusual or peculiar unsafe conditions hazardous to persons and property.
13. Bidder expressly acknowledges that it is aware of such peculiar risks and that it has the skill and experience to foresee and to adopt protective measures to adequately and safely perform the Work with respect to such hazards.
14. Bidder expressly acknowledges that it is aware that if a false claim is knowingly submitted (as the terms "claim" and "knowingly" are defined in the California False Claims Act, Gov. Code, § 12650 et seq.), the District will be entitled to civil remedies set forth in the California False Claim Act. It may also be considered fraud and the Contractor may be subject to criminal prosecution.
15. The undersigned Bidder certifies that it is, at the time of bidding, and shall be throughout the period of the Contract, licensed by the State of California to do the type of work required under the terms of the Contract Documents and registered as a public works contractor with the Department of Industrial Relations. Bidder further certifies that it is regularly engaged in the general class and type of work called for in the Contract Documents.

Furthermore, Bidder hereby certifies to the District that all representations, certifications, and statements made by Bidder, as set forth in this bid form, are true and correct and are made under penalty of perjury.

Dated this _____ day of _____ 20 ____

Name of Bidder: _____

Type of Organization: _____

Signature: _____

Print Name: _____

Title: _____

Address of Bidder: _____

Taxpayer Identification No. of Bidder: _____

Telephone Number: _____

Fax Number: _____

E-mail: _____ Web Page: _____

Contractor's License No(s): No.: _____ Class: _____ Expiration Date: _____

No.: _____ Class: _____ Expiration Date: _____

No.: _____ Class: _____ Expiration Date: _____

Public Works Contractor Registration No.: _____

END OF DOCUMENT