



MARK	FIXTURE	S OR H	V.	C. H.	H. H.	DESCRIPTION
EV-2	FLUSH VALVE	-	-	1"	-	SLON "ROYAL" #110-3 FLUSH VALVE.
WC-1	WATER CLOSET	-	-	-	-	OLSONITE #95C/55 OPEN-FRONT SEAT.
HB-1	HOSE BIBB	-	-	3/4"	-	ACORN #8121 ROUGH BRONZE WALL HOSE VALVE WITH VANDOL ROOF LOCKSHIELD, VANDOL BREAKER, AND REMOVABLE HANDLE.
HB-2	HOSE BIBB	-	-	3/4"	-	CHICAGO #952 POLISHED CHROME WITH LOCKSHIELD VANDOL BREAKER AND REMOVABLE HANDLE.
LT-1	LAVATORY TRIM	-	-	1/2"	-	CHICAGO #335-412 FACET AND AMERICAN STANDARD #2411.015 GRID MOUNT.
SP-1	SUMP PUMP	-	-	-	-	BRUNNEN "THE BOSS" #290 STAINLESS STEEL SUMP PUMP WITH REVERSE OPERATION, 1/3 HP, 120V/1 PHASE, 22 GPM AT 14 FT. HEAD.

MARK	FIXTURE	S OR H	V.	C. H.	H. H.	DESCRIPTION
EV-1	FLUSH VALVE	-	-	3/4"	-	SLON "ROYAL" #106-11 FLUSH VALVE.
WC-1	WATER CLOSET	4"	2"	1"	-	AMERICAN STANDARD #8221.018 WATER-SAVING MODERN FLUSH VALVE AND OLSONITE #95C/55 OPEN-FRONT SEAT.
WC-2	WATER CLOSET	4"	2"	1"	-	KOHLER #4202-ET W/SCAV #105-5 FLUSH VALVE & L-100C 2" HIGH LIFT SEAT.
UR-1	URINAL	2"	1-1/2"	1"	-	AMERICAN STANDARD "TALBROOK" #6540.017 W/SLON "ROYAL" #180 FLUSH VALVE, AND JAY R. SMITH #634 SUPPORT CARRIER.
UR-2	URINAL	2"	1-1/2"	1"	-	SAME AS UR-1 EXCEPT MOUNT AT HANDICAP HEIGHT.
LA-1	LAVATORY	2"	1-1/2"	1/2"	-	AMERICAN STANDARD "NEW LUCERNE" #0356.421, 20" X 18" W/2411.015 EIP-TAP DRINK, SELF-CHECKING #335-412 INFERRED "C" AND JAY R. SMITH #700-2 SUPPORT CARRIER, ADJUST FACET TO 5/8" OPEN FOR 10 SECONDS.
LA-2	LAVATORY	2"	1-1/2"	1/2"	-	SAME AS LA-1 EXCEPT MOUNT AT HANDICAP HEIGHT.
CS-1	CLASSROOM SINK	2"	1-1/2"	1/2"	-	HAAS #4110, 24" X 15" ENAMELED CAST IRON W/CHICAGO #390 PAINTY FACET FRONT, CHICAGO #335-412 W/FINISHED FLOOR, PROVIDE TRAP, PRIMER CONNECTION WHEN APPLICABLE. AND #6455 SINK STRAINER.
SI-1	SINK TRIM	-	-	1/2"	-	CHICAGO #390 PAINTY FACET HUNGRO "C" AT LEFT REAR, CHICAGO #749-335 DRINKING BUBBLER AT RIGHT FRONT.
FD-1	FLOOR DRAIN	2"	1-1/2"	-	-	JAY R. SMITH #700-B, W/5" SQUARE MICHEL BRONZE STRAINER, PROVIDE TRAP PRIMER CONNECTION WHEN APPLICABLE.
FS-1	FLOOR SINK	-	-	1/2"	-	JAY R. SMITH #3100-12C, B-1/2" X 6-1/2" W/FLASHING CLAMP AND SEE PLAN FOR SINK STRAINER, W/FINISHED FLOOR, PROVIDE TRAP, PRIMER CONNECTION WHEN APPLICABLE.
TP-1	TRAP PRIMER	-	-	1/2"	-	PRECISION PLUMBING PRODUCTS MODEL #P-1 VALVE W/DISTRIBUTION UNITS AS REQUIRED FOR UP TO 4 DRAINS.
DF-1	DRINKING FOUNTAIN	2"	1-1/2"	1/2"	-	WESTERN #11-4WC WALL-MOUNT FOR MECHANICAL ACCESS W/NO DISH-WASHER VALVES, AND JAY R. SMITH #824 SUPPORT CARRIER.
WH-1	WATER HEATER	-	-	3/4"	3/4"	A. O. SMITH #40-6, 6 GALLON STORAGE CAPACITY, AND 3/4" X 1/2" RELIEF VALVE, OPERATING WEIGHT = 80 LBS.

ROOSEVELT SCHOOL MODERNIZATION
 FOR
 BAKERSFIELD CITY SCHOOL DISTRICT
BUILDING 100 PLUMBING PLAN
bfgc architects planners inc.
 P.O. Box 86681, 3535 S. Central Expressway, Suite 200, Bakersfield, CA 93315
 (805) 832-8122
 DR. GONZALES
 C-3132 C-6564 C-8021 C-8702

Donald R. Lawrence & Associates
 CONSULTING MECHANICAL ENGINEERS INCORPORATED
 2000 24th Street, Suite 100, Bakersfield, CA 93311
 805-338-1111
 D. OUSTAD
 2.00