ROOM FINISH SCHEDULE

MATERIALS

1. CERAMIC TILE
2. VINYL COMPOSITION TILE
3. CARPET
4. 6" COVED CERAMIC TILE BASE
5. 4" RUBBER BASE (CARPET BASE AT CARPET TOPSET BASE AT VINYL FLOORING)
6. EXISTING PLASTER
7. 5/8" GYP. BD. W/ VENEER PLASTER (MATCH (E) ADJACENT PLASTER TEXTURE)
8. 3/4" LATH AND PLASTER
9. VINYL COVERED TACKABLE WALL PANELS
10. T-BAR AND ACOUSTICAL PANELS
11. EXISTING T-BAR CEILING GRID
12. LAY-IN ACOUSTIC CEILING PANELS.
13. EXISTING ACOUSTIC CEILING TILE. REPLACE ANY EXPOSED DAMAGED TILES WITH MATCHING TEXTURE & PATTERNED ACOUSTIC CEILING TILE.
14. EXISTING PLYWOOD

FINISH

A. FACTORY
B. NONE
C. PAINT – GLOSS
D. PAINT – SEMI-GLOSS
E. INTEGRALLY COLORED
F. STAIN AND LACQUER
G. CLEAN AND PAINT
H. PAINT TO MATCH (E) ADJACENT SURFACE
J. CLEAN AND WAX

NO.	ROOM NAME	FLR. MAT.	FLR. FIN.	BASE MAT.	BASE FIN.	WALL NORTH MAT.	WALL NORTH FIN.	WALL EAST MAT.	WALL EAST FIN.	WALL SOUTH MAT.	WALL SOUTH FIN.	WALL WEST MAT.	WALL WEST FIN.	CEIL. MAT.	CEIL. FIN.	CEIL. HGT.	NO.	REMARKS
BUILDING A																		
22A1	HANDICAP LIFT	2	J	6	A	6	D	6/8	D	6/8	D	6	D	6/8	D	VARIES	28A1	PAINT - GLOSS (E) DOOR JAMB & TRIM
17A2	PLATFORM	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	17A2	
28A3	CORRIDOR	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	28A3	
16A4	MULTI-PURPOSE	–	–	–	–	–	–	–	–	–	–	6/8	H/H	–	–	VARIES	16A4	REFER TO FLOOR PLAN SHEET A-2 FOR EXISTING OF PAINTING AT WALLS
20A5	WOMEN	1	A	4	A	1	A	1	A	1	A	1	A	6	D	±8'-0"	20A5	PAINT - GLOSS (E) DOOR JAMBS & TRIM
20A6	MEN	1	A	4	A	1	A	1	A	1	A	1	A	6	D	±8'-0"	20A6	PAINT - GLOSS (E) DOOR JAMBS & TRIM
1A7	CONFERENCE	2/8	A	5	A	6	D	6	D	6	D	6	D	13	A	±9'-6"	1A7	PAINT - GLOSS (E) WINDOW & JAMBS, SILLS, TRIM
28A8	CORRIDOR	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	28A8	
14A9	DISHWASHER	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	14A9	
19A10	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19A10	
20A11	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	20A11	
19A12	MECHANICAL	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19A12	
28A13	WALK-IN COOL STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	28A13	
19A14	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19A14	
13A15	KITCHEN	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	13A15	
BUILDING B																		
1B1	RECEPTION	–	–	–	–	–	–	–	–	–	–	–	–	13	A	±11'-6"	1B1	
1B2	MIMEO	–	–	–	–	–	–	–	–	–	–	–	–	13	A	±11'-6"	1B2	
1B3	SUPPLY	–	–	–	–	–	–	–	–	–	–	–	–	13	A	±11'-6"	1B3	
19B4	BOOK STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±11'-6"	19B4	
19B5	MECHANICAL	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19B5	
1B6	TEACHERS WORK SPACE	–	–	–	–	–	–	–	–	–	–	–	–	13	A	±11'-6"	1B6	
19B7	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19B7	
19B8	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19B8	
20B9	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±8'-6"	20B9	
20B10	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±11'-6"	20B10	
1B11	HEALTH	–	–	–	–	–	–	–	–	–	–	–	–	13	A	±11'-6"	1B11	
1B12	VICE PRINCIPAL	–	–	–	–	–	–	–	–	–	–	–	–	13	A	±11'-6"	1B12	
28B13	CORRIDOR	–	–	–	–	–	–	–	–	–	–	–	–	13	A	±8'-0"	28B13	
19B14	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19B14	
19B15	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19B15	
20B16	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±11'-6"	20B16	
1B17	PRINCIPAL	–	–	–	–	–	–	–	–	–	–	–	–	13	A	±11'-6"	1B17	
23B18	KINDERGARTEN	2/3	J/A	5	A	14	D	14	D	14/9	D/A	14/9	D/A	10/13	A	V-B/VAR	23B18	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
20B19	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±8'-6"	20B19	
20B20	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±8'-6"	20B20	
20B21	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±8'-6"	20B21	
20B22	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±8'-6"	20B22	
20B23	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±8'-6"	20B23	
19B24	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	13	H	±8'-6"	19B24	
19B25	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	13	H	±8'-6"	19B25	
23B26	KINDERGARTEN	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	6/14	D	10/13	A	V-B/VAR	23B26	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
BUILDING C																		
25aC1	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aC1	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aC2	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aC2	" " " " " " " "
25aC3	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aC3	" " " " " " " "
19C4	BOOK STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19C4	
19C5	JANITOR	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19C5	
25aC6	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aC6	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aC7	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aC7	" " " " " " " "
20C8	GIRLS	–	–	–	–	–	–	–	–	–	–	–	–	6	H	VARIES	20C8	
19C9	MECHANICAL	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19C9	
20C10	BOYS	–	–	–	–	–	–	–	–	–	–	–	–	6	H	VARIES	20C10	
		–	–	–	–	–	–	–	–	–	–	–	–	–	–	–		
		–	–	–	–	–	–	–	–	–	–	–	–	–	–	–		
BUILDING D																		
25aD1	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aD1	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aD2	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aD2	" " " " " " " "
25aD3	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aD3	" " " " " " " "
20D4	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	VARIES	20D4	
20D5	TOILET ALCOVE	–	–	–	–	–	–	–	–	–	–	–	–	13	A	VARIES	20D5	
22D6	TEACHER'S LOUNGE	3	A	(E)	C	9/6	A/D	6	D	6	D	6	D	13	A	VARIES	22D6	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aD7	PRIMARY CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aD7	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aD8	PRIMARY CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aD8	" " " " " " " "
20D9	GIRLS	1	A	4	A	6/1	D/A	6/1	D/A	6/1	D/A	6/1	D/A	6	D	VARIES	20D9	" " " " " " " "
20D10	MEN'S LOUNGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	20D10	
20D11	TOILET	–	–	–	–	–	–	–	–	–	–	–	–	6	H	±8'-6"	20D11	
20D12	BOYS	1	A	4	A	6/1	D/A	6/1	D/A	6/1	D/A	6/1	D/A	6	D	VARIES	20D12	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS TRIM
BUILDING E																		
25aE1	CLASSRM.	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aE1	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aE2	CLASSRM.	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aE2	" " " " " " " "
25aE3	CLASSRM.	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aE3	" " " " " " " "
19E4	BOOK STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19E4	
19E5	JANITOR	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19E5	
25aE6	CLASSRM.	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aE6	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aE7	CLASSRM.	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aE7	" " " " " " " "
20E8	GIRLS	1	A	4	A	6/1	D/A	6/1	D/A	6/1	D/A	6/1	D/A	6	D	VARIES	20E8	" " " " " " " "
19E9	MECHANICAL EQUIP.	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19E9	
20E10	BOYS	1	A	4	A	6/1	D/A	6/1	D/A	6/1	D/A	6/1	D/A	6	D	VARIES	20E10	PAINT - GLOSS (E) WINDOW & DOOR JAMBS, SILLS, TRIM
2F1	ARTS / CRAFTS CLASSROOM	2	J	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	2F1	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aF2	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aF2	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25aF3	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	10/13	A	V-B/VAR	25aF3	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM
19F4	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19F4	
19F5	STORAGE	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	19F5	
BUILDING R-2																		
25bR21	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	13	A	±10'-2"	25bR21	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25bR22	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	13	A	±10'-2"	25bR22	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25bR23	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	13	A	±10'-2"	25bR23	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25bR24	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	13	A	±10'-2"	25bR24	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM
BUILDING R-5																		
25bR51	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	13	A	±10'-2"	25bR51	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM
25bR52	CLASSROOM	2/3	J/A	5	A	14	D	14/9	D/A	14/9	D/A	14	D	13	A	±10'-2"	25bR52	PAINT - GLOSS, (E) WINDOW & DOOR JAMBS, SILLS, TRIM

RRA
Architecture
Planning
Interior Design
Space Planning

Donald W. Renfro AIA C5283
Mark E. Russell AIA C13726
Carl G. Elliott AIA C7571
K. Bartram Huffman AIA C12061
Kenneth A. Kalla AIA C17760
Jeffrey P. Krausse AIA C16834
Tommy W. Preston AIA C12263
Larry G. Wiggins AIA C12514

Renfro-Russell & Associates, Inc.
4800 Stockdale Highway, Suite 304, Bakersfield, California 93309 (805) 327-7075

CONSULTANTS

PROJECT

BAKERSFIELD CITY SCHOOL DISTRICT

FREMONT ELEMENTARY SCHOOL MODERNIZATION

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT. ANY USE WITH WHICH, CONTACT WITH OTHERS MAY BE MADE OF THESE DRAWINGS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

KEY PLAN



BAKERSFIELD CITY SCHOOL DISTRICT
BOARD OF EDUCATION

DATE	APPROVED

DATE	ISSUED FOR
9.3.91	BIDDING

DATE	REVISIONS

SHEET TITLE

ROOM FINISH SCHEDULE

APPROVED/ARCHITECT Tommy W. Preston
CHECKED TWP DATE 8-1-89
DRAWN BY RSS,ES PROJECT NO. 86-216FM

SHEET NUMBER 86216CA82A96

A-8

OF 19 SHEETS

OFFICE OF THE STATE ARCHITECT
AUG 01 89
APPLICATION FILE NO. AND DATE
IDENTIFICATION STAMP
Department of General Services
Office of the State Architect
DEC 13 1990
Structural Safety Section
Appl. # 491550 NP/L4
STATE OF CALIFORNIA
SOUTHERN REGION