STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF ARCHITECTURE

SCALE: 1/2" = 1'-0"

APPROVED
S-5-49

BAKERSFIELD CITY SCHOOL DIST.
BOARD OF EDUCATION
APPROVED

BAKERSFIELD CITY SCHOOL DIST.
SUPERINTENDENT OF CITY SCHOOLS
RECOMMENDED FOR APPROVAL

Superintendent
Date

Secretary
Date

Architect
Date

5/4/49
DRAWN

WRIGHT METCALF & PARSONS
111 MORAN BUILDING BAKERSFIELD, CALIFORNIA

J. Lloyd Wright C-277

5/4/49
DATE

JOB 103

SHEET 5

ROOF PLAN-INTERIOR ELEVATIONS & DETAILS
YOUNT-EANON (4) SCHOOL-ADDITIONS
BAKERSFIELD CITY SCHOOL DISTRICT

CABINET
NORTH WALL CLASS. RM.

ELEVATIONS A-A, B-B, C-C, D-D
SCALE 1/2" = 1'-0"

WEST END OF CLASS ROOM PLAN
SCALE 3/8" = 1'-0"

EAST ELEVATION

INTERIOR ELEVATIONS OF TYPICAL CLASS ROOM
SCALE 3/8" = 1'-0"

SOUTH ELEVATION

EAST ELEVATION

NORTH ELEVATION

WEST ELEVATION

ROOF PLAN
SCALE 1/32" = 1'-0"

Existing bldg. line

Note: All toilet seats shall be securely anchored at top to wall to prevent overturning.

ADDITION TO ADMINISTRATION ROOF PLAN

TYPICAL BASE & SHOE
- FULL SIZE TRIM ALL ROOMS

CHALK RAIL

CEILING TRIM ALL ROOMS

HEAD RAIL
STILES SIMILAR

F/S MULLION TRIM

F/CLASS. DBL. DOOR TRIM

F/TYP. BATTEN & TRIM

INSIDE CORNER WHERE BLACKBOARD OCCURS

TYPICAL INSIDE VERTICAL CORNER ALL ROOMS

INSULATION BOARD

SCHEDULE OF HEIGHTS CLASSROOM MILLWORK ETC.

ROOM	DIMENSION A	DIMENSION B	DIMENSION C	DIMENSION D
1	2'-4"	2'-0"	2'-4"	0"
2	"	"	"	"
3	"	"	"	"
4	"	"	"	"
5	"	"	"	"
6	"	"	"	"
7	"	"	"	"
8	"	"	"	"
9	"	"	"	"
10	"	"	"	"
11	2'-0"	1'-9"	2'-0"	12"
12	"	"	"	"
13	"	"	"	"
14	"	"	"	"
15	"	"	"	"
16	"	"	"	"
17	2'-0"	1'-9"	2'-0"	12"
18	"	"	"	"
19	"	"	"	"
20	"	1'-9"	2'-0"	12"