## MATERIAL AND FINISH DESIGNATIONS

REFER TO ABBREVIATIONS, SHEET A0.01 FOR ADDITIONAL INFORMATION
NOT ALL DESIGNATIONS MAY OCCUR ON THIS SHEET

### FLOOR MATERIAL DESIGNATIONS

CT – CERAMIC TILE
VCT – VINYL COMPOSITION TILE
CONC – EXPOSED CONCRETE
QT – QUARRY TILE

### CEILING MATERIAL DESIGNATIONS

ACT – ACOUSTICAL CEILING PANEL
T&T – SUSPENDED ACOUSTICAL CEILING
PLAS – PLASTER

### MISCELLANEOUS DESIGNATIONS

MIR – MIRROR
GRT – GROUT
FP – SPRAYED FIRE PROOFING
INTU – INTUMESCENT PAINT
WD – WOOD
GB – GYPSUM BOARD

### BASE MATERIAL DESIGNATIONS

CTB – CERAMIC TILE BASE
TSB – TOP SET BASE

### FINISH DESIGNATIONS

HS – HARDNER/SEALER
E – ENAMEL PAINT
ST – STAIN
P – PAINT
FAC – FACTORY APPLIED FINISH
INT – INTEGRAL FINISH
PF – PREFINISHED

### WALL MATERIAL DESIGNATIONS

AWSF – ACOUSTICAL WALL SYSTEM FABRIC COVERED
FCTP – FABRIC COVERED TACKABLE PANEL
VCTP – VINYL COVERED TACKABLE PANEL
FCAP – FABRIC COVERED ACOUSTICAL PANEL
TWSF – TACKABLE WALL SYSTEM FABRIC COVERED
TWSV – TACKABLE WALL SYSTEM VINYL COVERED
TWSA – ACOUSTICAL TACKABLE WALL SYSTEM FABRIC COVERED
FWC – FABRIC WALL COVERING
VWC – VINYL WALL COVERING
PL – PLASTIC LAMINATE
PLCC – PLASTIC LAMINATE COLOR CORE
PLHD – PLASTIC LAMINATE HIGH DENSITY
PLCR – PLASTIC LAMINATE CHEMICAL RESISTANT
PLY – 3/4" THICK PLYWOOD
FRP – FIBERGLASS REINFORCED POLYESTER PANELS
MDO – MEDIUM DENSITY OVERLAY PLYWOOD
GLBL – GLASS BLOCK

## GENERAL NOTES

1. REFER TO INTERIOR ELEVATIONS FOR LOCATIONS OF WALL DEVICES, I.E. MARKER BOARDS, TACKABLE PANELS, ACOUSTICAL PANELS, ETC.
2. REFER TO DETAIL 20/A10.02 FOR FLOOR MATERIAL CHANGES
3. REFER TO REFLECTED CEILING PLAN FOR CEILING HEIGHTS OF INDIVIDUAL ROOMS
4. ALL INTERIOR FINISHES SHALL COMPLY WITH CBC CHAPTER 8, CBC SECTION 1103, 3.3 AND TITLE 19 CCR.
5. PATCH & REPAIR FLOOR AND CEILING TO MATCH EXISTING.

## ROOM FINISH SCHEDULE - BUILDING 100

| NO | ROOM NAME | FLOOR MATERIAL | FLOOR FINISH | BASE MATERIAL | BASE FINISH | WALLS 1 MATERIAL | WALLS 1 FINISH | | WALLS 2 MATERIAL | WALLS 2 FINISH | | WALLS 3 MATERIAL | WALLS 3 FINISH | | WALLS 4 MATERIAL | WALLS 4 FINISH | | CEILING MATERIAL | CEILING FINISH | NOTES | NO |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 1 | 1 | 1 | 1 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 1 | | |
| 101 | PUBLIC AREA | VCT | PF | TSB | PF | (E) FCTP | -- | PF | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) ACT | PF | -- | 101 |
| 102 | SECRETARY | VCT | PF | TSB | PF | (E) FCTP | -- | PF | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) ACT | PF | -- | 102 |
| 103 | ~~PRINCIPAL~~ | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) ACT | PF | -- | 103 |
| 104 | COUNSELOR | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) ACT | PF | -- | 104 |
| 105 | NURSE | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | PLWD | -- | E | -- | (E) ACT | PF | -- | 105 |
| 106 | TOILET | CT | PF | CTB | PF | PLAS | CT | E | CT | PLAS | CT | E | CT | PLAS | CT | E | CT | PLAS | CT | E | CT | PLAS | E | -- | 106 |
| 107 | MEN | (E) CT | PF | (E) CTB | PF | (E) PLAS | (E) CT | E | (E) CT | (E) PLAS | (E) CT | E | (E) CT | (E) PLAS | (E) CT | E | (E) CT | (E) PLAS | (E) CT | E | (E) CT | (E) PLAS | E | -- | 107 |
| 108 | WOMEN | (E) CT | PF | (E) CTB | PF | (E) PLAS | (E) CT | E | (E) CT | (E) PLAS | (E) CT | E | (E) CT | (E) PLAS | (E) CT | E | (E) CT | (E) PLAS | (E) CT | E | (E) CT | (E) PLAS | E | -- | 108 |
| 109 | FACULTY | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 109 |
| 110 | BOOK & SUPPLY | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 110 |
| 111 | VISUAL | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 111 |
| 112 | ~~CONFERENCE~~ | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 112 |
| 113 | RECEPTION | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 113 |
| 114 | NURSE CLOSET | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) ACT | PF | -- | 114 |

## ROOM FINISH SCHEDULE - BUILDING 200

| NO | ROOM NAME | FLOOR MATERIAL | FLOOR FINISH | BASE MATERIAL | BASE FINISH | WALLS 1 MATERIAL | WALLS 1 FINISH | | WALLS 2 MATERIAL | WALLS 2 FINISH | | WALLS 3 MATERIAL | WALLS 3 FINISH | | WALLS 4 MATERIAL | WALLS 4 FINISH | | CEILING MATERIAL | CEILING FINISH | NOTES | NO |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 1 | 1 | 1 | 1 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 1 | | |
| 201 | MULTI-PURPOSE | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) T&T | PF | -- | 201 |
| 202 | KITCHEN | (E) VCT | PF | (E) TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 202 |
| 203 | FACULTY DINING | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) T&T | PF | -- | 203 |
| 204 | DISHWASHING | (E) QT | PF | (E) CTB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 204 |
| 205 | COLD BOX | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | No work req'd. | 205 |
| 206 | DRY STORAGE | (E) VCT | PF | (E) TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 206 |
| 207 | MECHANICAL | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | No work req'd. | 207 |
| 208 | CUSTODIAL | (E) VCT | PF | (E) TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 208 |
| 209 | PLATFORM | (E) VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 209 |
| 210 | DRESSING | WD | HS | TSB | PF | GB | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | 5 | 210 |
| 211 | STORAGE | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 211 |
| 212 | MEN | (E) CT | PF | (E) CTB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 212 |
| 213 | WOMEN | (E) CT | PF | (E) CTB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 213 |
| 214 | TOILET | (E) CT | PF | (E) CTB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 214 |
| 215 | COMPACTOR RM. | (E) CONC | HS | (E) CONC | HS | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 215 |
| 216 | CAN WASH | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | No work req'd. | 216 |
| 217 | LOCKERS | (E) VCT | PF | (E) TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 217 |
| 218 | JANITOR | (E) VCT | PF | (E) TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 218 |
| 219 | VESTIBULE | (E) VCT | PF | (E) TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) ACT | PF | -- | 219 |
| 220 | LIFT VESTIBULE | VCT | PF | TSB | PF | (E) PLAS | PLAS | E | E | (E) PLAS | PLAS | E | E | GB | -- | E | -- | (E) PLAS | PLAS | E | E | (E) PLAS | E | 5 | 220 |

## ROOM FINISH SCHEDULE - BUILDING 300

| NO | ROOM NAME | FLOOR MATERIAL | FLOOR FINISH | BASE MATERIAL | BASE FINISH | WALLS 1 MATERIAL | WALLS 1 FINISH | | WALLS 2 MATERIAL | WALLS 2 FINISH | | WALLS 3 MATERIAL | WALLS 3 FINISH | | WALLS 4 MATERIAL | WALLS 4 FINISH | | CEILING MATERIAL | CEILING FINISH | NOTES | NO |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 1 | 1 | 1 | 1 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 1 | | |
| 301 | KINDERGARTEN | VCT | PF | TSB | PF | (E) PLAS | PLWD | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLWD | -- | E | -- | T&T | PF | -- | 301 |
| 302 | KINDERGARTEN | VCT | PF | TSB | PF | (E) PLAS | PLWD | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLWD | -- | E | -- | T&T | PF | -- | 302 |
| 303 | WORK ROOM | VCT | PF | TSB | PF | (E) PLAS | PLWD | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 303 |
| 304 | WORK ROOM | VCT | PF | TSB | PF | (E) PLAS | PLWD | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 304 |
| 305 | FAN ROOM | (E) CONC | HS | (E) CONC | HS | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 305 |
| 306 | TOILET | (E) CT | PF | (E) CTB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 306 |
| 307 | TOILET | CT | PF | CTB | PF | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | E | -- | 307 |
| 308 | WASH AREA | CT | PF | CTB | PF | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | E | -- | 308 |
| 310 | TOILET | CT | PF | CTB | PF | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | -- | E | -- | PLAS | E | -- | 310 |
| 311 | TOY STORAGE | (E) CONC | HS | (E) CONC | HS | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 311 |

## ROOM FINISH SCHEDULE - BUILDING 400

| NO | ROOM NAME | FLOOR MATERIAL | FLOOR FINISH | BASE MATERIAL | BASE FINISH | WALLS 1 MATERIAL | WALLS 1 FINISH | | WALLS 2 MATERIAL | WALLS 2 FINISH | | WALLS 3 MATERIAL | WALLS 3 FINISH | | WALLS 4 MATERIAL | WALLS 4 FINISH | | CEILING MATERIAL | CEILING FINISH | NOTES | NO |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 1 | 1 | 1 | 1 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 2 | 1 | 1 | | |
| 401 | LIBRARY | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | (E) GB | E | E | T&T | PF | -- | 401 |
| 402 | CLASSROOM | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | (E)GB | E | E | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | T&T | PF | -- | 402 |
| 403 | CLASROOM | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | T&T | PF | -- | 403 |
| 404 | CLASSROOM | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | T&T | PF | -- | 404 |
| 405 | CLASSROOM | VCT | PF | TSB | PF | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | (E) PLWD | -- | E | -- | T&T | PF | -- | 405 |
| 406 | TEACHERS WORKROOM | VCT | PF | TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 406 |
| 407 | BOYS TOILET | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | No work req'd. | 407 |
| 408 | GIRLS TOILET | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | No work req'd. | 408 |
| 409 | STORAGE | (E) CONC | HS | (E) TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 409 |
| 410 | STORAGE | (E) CONC | HS | (E) TSB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 410 |
| 411 | TOILET | (E) CT | PF | (E) CTB | PF | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | -- | E | -- | (E) PLAS | E | -- | 411 |
| 412 | HEATER ROOM (TYP.) | (E) CONC | HS | (E) PLAS | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | 412 |
| 413 | HEATER ROOM | (E) CONC | HS | (E) PLAS | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | 413 |
| 414 | HEATER ROOM | (E) CONC | HS | (E) PLAS | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | 414 |
| 415 | HEATER ROOM | (E) CONC | HS | (E) PLAS | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | 415 |
| 416 | HEATER ROOM | (E) CONC | HS | (E) PLAS | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | -- | (E) PLAS | -- | -- | 416 |

Item ( 7)
#1

Refer to Architectural Drawings, Sheets A2.11, A2.21, A2.31, A2.41, A2.51, A2.61, A5.11 and A5.12:

a. **CLARIFY** the **REMOVAL** of existing finish materials for surfaces listed below shall NOT be a part of this project and REPLACEMENT of finish materials (as identified on the Room Finish Schedules shall be included as a part of this project:

Building 100

Floor - Secretary (102), Public Area (101), Principal (103), Counselor (104), Nurse (105), Faculty Workroom (109), Book and Supply Room (110), Visual Aid (111) and Reception (113).

Walls - Toilet (106), Men (107) and Women (108)

Building 200

Floor Faculty Dining (203)

Building 300

Floor - Kindergarten (301), Kindergarten (302), Workroom (303) and Workroom (304).

Walls - Toilet (307 ), Wash Area (308) and Toilet (310)

Building 400

Floor - Library (401), Classrooms (402-405) and Teachers Workroom (406)

Building 500

Walls - Boys (501) and Girls (505)

Building 600

Floor - Classrooms (601-604), Teachers Lounge (605) and Classrooms (608-613).

Walls - Women (606) and Men (607)

b. **REMOVE** and **REPLACE**, as a part of the work, existing finish materials with new finish materials as indicated on "Room Finish Schedules" for the following rooms:

Building 100

Floor – Toilet (106), Conference (112) and Nurse Closet (114).

Building 200

Floor – Multipurpose (201), Storage (211) and Lift Vestibule (220 ).

Building 300

Floor – Toilet (307), Wash Area (308) and Toilet (309).

c. In conjunction with installation of new suspended acoustical ceilings in Room Nos. 301, 302, 401-405, 601-604 and 608-613, **PROVIDE** the following alterations to the existing HVAC system:

1) **REMOVE** (E) supply air registers.
2) **ADD** square to round sheet metal transition at (E) supply air register locations.
3) **ADD** 7'-0" x 10" dia. flex duct with factory ends from transitions to ceiling register.
4) **ADD** four (4) "Nailor" Model 7500-L (T-bar mounted) modular core diffusers with O.B.D. (12" x 12" with 10" dia. neck adaptor).
5) **ADD** transition as required from (E) return air grille to 16" dia.
6) **ADD** 7'-0" x 16" dia. flex duct with factory ends to ceiling return air grille.
7) **ADD** one (1) "Nailor" Model 51EC-L with 16" dia. neck adaptor.

d. **ADD** carpet to Kindergartens (301 and 302) as shown on attached Drawing AD1-01, dated 8/3/07. See A 1.01

e. **ADD** to the scope of work, repainting of the exterior of all buildings (Buildings 100-600) including walls, doors / door frames, windows and building trims.

f. **ADD** 4'-0" x 6'-0" walk-off carpet mat (Abrasive Action) outside each classroom (301, 302, 402-405, 601-604 and 608-613). Edges of carpet mat shall be finished.

g. **CLARIFY** Contractor shall **PROVIDE** ceramic tile for Room Nos. 307, 308, 310, 606 and 607 (as shown on Architectural Drawings, Sheet A9.62).


bfgc Architecture

**Bakersfield**
5500 ming avenue, suite 450, bakersfield, ca 93309
661.836.4300 fax 661.836.4311

**San Jose**
150 south first st., suite 200
san jose, california 95113
408.924.0841
fax 408.924.0844

**San Luis Obispo**
4115 broad street, suite b-6
san luis obispo, ca 93401
805.546.0433
fax 805.546.0504

**Oakland**
350 frank ogawa plaza., suite 300
oakland, california 94612
510.891.0670
fax 510.891.0674

**Principal Architects**
david r. cartwell, f.a.i.a., C-6564
frank a. ghezzi, a.i.a., C-3132
mark engellen, a.i.a., C-8021
william r. tucoulet, a.i.a., C-8702
dean a. tatzeuno, a.i.a., C- 9190
bruce m. biggar, a.i.a., C-23134
brad henderson, a.i.a., C-10901
richard l. mello, a.i.a., C-18079


LICENSED ARCHITECT STATE OF CALIFORNIA

FILE NO: 15-6

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT
APPL NO: 01-106663
AC 1A FLS 11 SS 12
DATE 06-24-03

# MODERNIZATION

**FOR**

HENRY EISSLER SCHOOL
2901 EISSLER STREET
BAKERSFIELD, CA 93306

BAKERSFIELD CITY SCHOOL DISTRICT

# BUILDING 100, 200, 300, & 400 ROOM FINISH SCHEDULES

| Version Date: | Version time: |
|---|---|
| job no. | 02-126 |
| date | 6-24-03 |
| drawn by | D.HERRERA |
| chk'd by | R.EDWARDS |
| ©copyright | 2003 |

A
5.11