



CLASSIFICATION OF SUSPENDED CEILING GRID:
 MANUFACTURER: CHICAGO METALLIC CORP.
 MAIN RUNNER: HEAVY DUTY 1870 F.R.
 CLASS: 1854
 CROSS RUNNER: REFER TO PROJECT MANUAL (SPECIFICATIONS) SECTION 09510 FOR ADDITIONAL INSTALLATION REQUIREMENTS OF SUSPENDED T-BAR CEILING SYSTEM.

NOTE:
 REMOVE EXISTING T-BAR CEILING AND ACROUSTICAL PANELS FROM ALL ROOMS IN BUILDINGS A, B, AND C.

SYMBOL/LEGEND	DESCRIPTION
2' x 4' SUSPENDED T-BAR CEILING SYSTEM WITH ACROUSTIC PANELS	EXISTING ACROUSTIC TILE CEILING
GRID BOARD CEILING (SEE ROOM FINISH SCHEDULE)	1' x 4' FLUORESCENT LIGHT FIXTURE (REFER TO ELECTRICAL LIGHTING PLAN)
2' x 4' FLUORESCENT LIGHT FIXTURE (REFER TO ELECTRICAL LIGHTING PLAN)	SUBP. MTD. INCANDESCENT LIGHT FIXTURE (REFER TO ELECTRICAL LIGHTING PLAN)
SUPPLY AIR REGISTER (REFER TO MECHANICAL PLAN)	RETURN AIR REGISTER (REFER TO MECHANICAL PLAN)
EXHAUST FAN REGISTER (REFER TO MECHANICAL PLAN)	

DEMOLITION NOTES

- ARROW INDICATES DIRECTION OF SLOPED CEILING FROM LOW TO HIGH
- ALL NOTES IN THIS COLUMN ARE TO BE USED FOR DRAWINGS ON THIS SHEET ONLY. NOTES LISTED IN THIS COLUMN WHICH ARE NOT INDICATED ON THE DRAWING SHALL BE DISREGARDED.
- REMOVE EXISTING LIGHT FIXTURES AND STOCKPILE IN DESIGNATED AREA FOR REVIEW BY OWNER FOR SALVAGE.
- REMOVE EXISTING LAY-IN ACROUSTIC CEILING PANELS AND STOCKPILE IN DESIGNATED AREA FOR REVIEW BY OWNER FOR SALVAGE.

REFLECTED CEILING PLAN NOTES

- ALL NOTES IN THIS COLUMN ARE TO BE USED FOR DRAWINGS ON THIS SHEET ONLY. NOTES LISTED IN THIS COLUMN WHICH ARE NOT INDICATED ON THE DRAWING SHALL BE DISREGARDED.
- EXISTING FURRED-IN ATTIC SPACE.
- EXISTING EXHAUST CHIMNEY.
- REPAIR EXISTING DRAPERY TRACKS.
- EXISTING ACROUSTIC CEILING TILE. REPLACE ANY MISSING OR DAMAGED TILES.
- REMOVE AND INSTALL REQUIRED CEILING STRIPPING AND MATCHING ACROUSTIC TILES.
- 2' x 4' LAY-IN ACROUSTICAL PANELS IN SUSPENDED T-BAR GRID. REFER TO DETAIL 1/A-10.
- REPAIR, CLEAN AND PAINT EXISTING SUSPENDED T-BAR CEILING SYSTEM AFTER EXISTING LAY-IN ACROUSTIC CEILING PANELS HAVE BEEN REMOVED.
- REPAIR PATCH AND PREPARE CEILING SURFACE TO ACCEPT FINISH. (REFER TO ROOM FINISH SCHEDULE.)
- CONTRACTOR SHALL VERIFY EXACT PLACEMENT OF CEILING REGISTER WITH ARCHITECT.
- REMOVE AND INSTALL 2' x 4' LAY-IN ACROUSTIC CEILING PANELS.
- REMOVE EXISTING ACROUSTIC TILES.

REFLECTED CEILING PLANS
 BUILDINGS A, B, C, DETAILS

1/8"

BAKERSFIELD CITY SCHOOL DISTRICT BOARD OF EDUCATION

FRANKLIN ELEMENTARY SCHOOL MODERNIZATION

Renfro-Russell & Associates, Inc.
 1000 S. Main Street, Suite 204, Bakersfield, California 93307 (805) 877-0700

CONSULTANTS:
 Donald W. Renfro, AIA
 Mark E. Russell, AIA
 Carl G. Elmer, AIA
 K. Burton Hillman, AIA
 Kenneth A. Kella, AIA
 Jeffrey P. Karsene, AIA
 Tommy W. Preston, AIA
 Larry G. Wiggins, AIA

PROJECT:
 BAKERSFIELD CITY SCHOOL DISTRICT
 FRANKLIN ELEMENTARY SCHOOL
 MODERNIZATION

KEY PLAN:
 MECHANICAL EQUIPMENT ENCLOSURE

DATE APPROVED: 5-11-84

DATE: 5-11-84

ISSUED FOR: ELECTRICAL

CHECKED: TYP
DRAWN BY: ES
SHEET NUMBER: A-10
OF 19 SHEETS