LEGEND

- EXISTING WALL TO REMAIN
- TYP. WALL @ BLDG. A: 2 X 6 WOOD STUDS @ 16" O.C. W/ 5/8" GYP. BOARD ONE SIDE & 1" EXTERIOR PLASTER @ OTHER SIDE W/ 5 1/2" BATT. INSULATION, ALSO W/ 6" HIGH CONC. CURB.
- TYP. WALL @ BLDG. B: 2 X 4 WOOD STUDS @ 16" O.C. W/ 5/8" GYP. BD. @ EACH SIDE
- TYP. WALL @ BLDG. C: 2 X 4 WOOD STUDS @ 16" O.C. WITH 5/8" GYP. BD. ON BOTH SIDES AND WITH 4'-8" CERAMIC TILE WAINSCOAT IN ONE SIDE, ALSO W/ 6" HIGH CONC. CURB.
- (E) WALL TO BE REMOVED
- (E) DOOR\FRAME TO BE REMOVED
- (E) DOOR/FRAME TO REMAIN

KEYNOTES

201 REMOVE (E) CABINETS
202 REMOVE (E) WALL
203 REMOVE (E) PLUMBING FIXTURE
204 REMOVE (E) CHALKBOARD
205 REMOVE (E) TACKBOARD
206 REMOVE (E) DOOR & FRAME
207 REMOVE (E) CARPET
208 REMOVE (E) CERAMIC TILE FLOOR
209 REMOVE (E) CERAMIC TILE WAINSCOT
210 REMOVE (E) DRINKING FOUNTAIN
211 REMOVE (E) BOILER
212 REMOVE (E) CONCRETE RAMP & HANDRAILS
213 REMOVE (E) COUNTERTOP & BASE CABINET SHELVES, REFINISH EXPOSED END OF CABINETS
214 REMOVE (E) FIRE HOSE CABINET
215 REMOVE (E) PEGBOARD WALL FACE
216 REMOVE (E) MAP RACK & SCREEN
217 REMOVE (E) ASPHALT PAVEMENT
218 CONCRETE RAMP AND WALKWAY
219 INFILL AND PATCH (E) DOOR OPENING, MATCHING THE SAME MATERIALS & FINISHES AS EXTERIOR WALLS
220 PATCH & FINISH WALL MATCH W/ SAME MATERIALS AND FINISHES AS EXISTING
221 PLATFORM LIFT
222 PLUMBING FIXTURE
223 CABINET SINK
224 3'-0" WOOD GATE W/ LATCH —MATCH (E) OFFICE FRONT DESK MATERIAL
225 WALL
226 2 X 6 STUDS W/ GYPSUM BOARD AND VENEER PLASTER (ONE SIDE) MATCH (E) FINISHES AND COLOR
227 H.M. DOOR AND FRAME SEE DOOR A



Item (4) Refer to Architectural Drawings, Sheet A2.02, and Plumbing Drawings, Sheet P2.01:

a. **PROVIDE** 6x6 HDR for Doors 222 and 223.

b. Contractor shall **PATCH AND REPAIR** existing south wall, Multi Purpose Room (201) after removal of existing cabinets.

c. Contractor shall **REMOVE** existing heating boiler in Boiler Room (B15), including all appurtenant piping, expansion tank, controls and flue through roof. Cap all utilities and flue through roof behind wall/ceiling surfaces.

d. Contractor shall **REMOVE** existing service sink in Janitor (B14) and **MODIFY** existing piping as required to accommodate mop sink (MS) as scheduled on Sheet P1.01.



NOTE: ALL DIMENSIONS SHOWN ARE EXISTING.

Item (10) Refer to Specification Section 14420 "Wheelchair Lifts", and Architectural Drawings, Sheets A2.02 and A3.06:

Contractor shall provide full-size door (3'-0" x 6'-8") with appropriate accessible door hardware on west side (lower level) of platform lift and manufacturer's standard lift gate on east side (upper level) of platform lift as an integral part of the platform lift.

Item (9) Refer to Architectural Drawings, Sheet A2.02, specifically Storage Room, B13:

a. Contractor shall **REMOVE** existing floor of Storage Room B13 as required to install platform lift. **PATCH AND REPAIR** existing floor material as required.

b. Walls on north and south side of platform lift to extend full height, floor to ceiling above. **PROVIDE** short wall (2x4 with gypsum board one side) at east side of platform from concrete floor to subfloor.



IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT
OFFICE OF REGULATION SERVICES
APPL 101118
AC FLS SS
DATE OCT 07 1998

bfgc architects planners inc.
bakersfield
5500 ming avenue, suite 450, bakersfield ca. 93309-4631
805 836-4300 fax 805 836-4311

san luis obispo
3211 broad street suite 113
san luis obispo, california 93401
805 546-0433

san jose
160 west santa clara st. suite 525
san jose, california 95113
408 924-0841

principal architects
david r. cartnal, f.a.i.a., C-6564
frank a. ghezzi, a.i.a., C-3132
mark engelen, a.i.a., C-8021
william r. tuculet, a.i.a., C-8702
dean a. tetsuno, a.i.a., C- 9190
bruce m. biggar, a.i.a., C-23134
brad a. henderson, a.i.a., C-10901
richard l. mello, a.i.a., C-18079

HORT SCHOOL MODERNIZATION

BAKERSFIELD CITY SCHOOL DISTRICT

2301 PARK DRIVE
BAKERSFIELD, CA. 93306

FLOOR PLAN

BUILDING B
1/8" = 1'-0"

job no.	97-276
date	JULY 8, 98
drawn by	J.L.G.
chk'd by	ROB T.
copyright	1997

A 2.02

PARTIAL FLOOR PLAN
BUILDING B

0 2 4 8 16 24

FLOOR PLAN - BUILDING B

0 2 4 8 16 24

KEY PLAN

PLOT DATE: 10-6-98
PATH\NAME: \LISA\DRAWING\97-276\DWG\776P202.dc5