



- CONSTRUCTION NOTES**
1. CONSTRUCT TYPE B CONCRETE CURB & GUTTER PER CITY OF BAKERSFIELD STANDARD S-1.
  2. CONSTRUCT STANDARD STREET CROSS CUTTER PER CITY OF BAKERSFIELD STANDARD S-17.
  3. REMOVE EXISTING A.C. PAVEMENT & CONSTRUCT 2" A.C. OVER 4" A.B. PER CITY OF BAKERSFIELD STANDARD S-25.
  4. CONSTRUCT HANDICAP RAMP WITH 1/4" HIGH LIP AT FLOW LINE ON 4.5% SLOPE PER CITY OF BAKERSFIELD STANDARD S-17.
  5. CONSTRUCT CONCRETE SIDEWALK PER CITY OF BAKERSFIELD STANDARD S-3. MATCH EXISTING SIDEWALK WITH - MINIMUM OF 5'.
  6. CONSTRUCT 2" A.C. OVER 4" A.B. OVER 6" NATIVE BAKERSFIELD STANDARD S-25.
  7. CONSTRUCT 6" WIDE CONCRETE CURB MONOLITHIC WITH HANDICAP RAMP-SEE DETAIL "E".
  8. CONSTRUCT 1/2" SQUARE HEAD ARROW SIGN OVER TYPE "M" OBJECT MARKER PER DETAIL "E".
  9. CONSTRUCT CONCRETE GUIDE CHANNEL FOR CHAIN LINK GATE PER DETAIL "C" AND SECTION "A-A".
  10. CONSTRUCT WALKWAY CURB PER DETAIL "B".

