MATERIAL AND FINISH DESIGNATIONS

REFER TO ABBREVIATIONS, SHEET A0.01 FOR ADDITIONAL INFORMATION
NOT ALL DESIGNATIONS MAY OCCUR ON THIS SHEET

FLOOR MATERIAL DESIGNATIONS

C – CARPET
CT – CERAMIC TILE
QT – QUARRY TILE
PT – PORCELAIN TILE
VAT – VINYL ASBESTOS TILE
VCT – VINYL COMPOSITION TILE
LT – LINOLEUM TILE
RT – RUBBER TILE
SL – SHEET LINOLEUM
SR – SHEET RUBBER
SV – SHEET VINYL
HSV – HOMOGENEOUS SHEET VINYL
SSV – SLIP-RESISTANT SHEET VINYL
SHSV – SLIP-RESISTANT HOMOGENEOUS SHEET VINYL
WD – WOOD FLOOR
CONC – EXPOSED CONCRETE
EPXY – EXPOSED EPOXY FLOOR

BASE MATERIAL DESIGNATIONS

CB – CARPET BASE
CTB – CERAMIC TILE BASE
QTB – QUARRY TILEBASE
PTB – PORCELAIN TILE BASE
TSB – TOP SET BASE
WDB – WOOD BASE
CSVB – COVED SHEET VINYL BASE
CLB – COVED LINOLEUM BASE
CRB – COVED RUBBER BASE
EPXY – COVED EPOXY BASE

WALL MATERIAL DESIGNATIONS

AWSF – ACOUSTICAL WALL SYSTEM FABRIC COVERED
FCTP – FABRIC COVERED TACKABLE PANEL
VCTP – VINYL COVERED TACKABLE PANEL
FCAP – FABRIC COVERED ACOUSTICAL PANEL
TWSF – TACKABLE WALL SYSTEM FABRIC COVERED
TWSV – TACKABLE WALL SYSTEM VINYL COVERED
TWSA – ACOUSTICAL TACKABLE WALL SYSTEM FABRIC COVERED
FWC – FABRIC WALL COVERING
VWC – VINYL WALL COVERING
PL – PLASTIC LAMINATE
PLCC – PLASTIC LAMINATE COLOR CORE
PLHD – PLASTIC LAMINATE HIGH DENSITY
PLCR – PLASTIC LAMINATE CHEMICAL RESISTANT
PLY – 3/4" THICK PLYWOOD
FRP – FIBERGLASS REINFORCED POLYESTER PANELS
MDO – MEDIUM DENSITY OVERLAY PLYWOOD
GLBL – GLASS BLOCK

CEILING MATERIAL DESIGNATIONS

ACT – ACOUSTICAL CEILING PANEL
T&T – SUSPENDED ACOUSTICAL CEILING
EXP – EXPOSED STRUCTURE

MISCELLANEOUS DESIGNATIONS

MIR – MIRROR
GRT – GROUT
FP – SPRAYED FIRE PROOFING
INTU – INTUMESCENT PAINT
WD – WOOD
GB – GYPSUM BOARD

FINISH DESIGNATIONS

HS – HARDNER/SEALER
E – ENAMEL PAINT
ST – STAIN
P – PAINT
FAC – FACTORY APPLIED FINISH
INT – INTEGRAL FINISH
PF – PREFINISHED

GENERAL NOTES

1. REFER TO INTERIOR ELEVATIONS FOR LOCATIONS OF WALL DEVICES, I.E. MARKER BOARDS, TACKABLE PANELS, ACOUSTICAL PANELS, ETC.
2. REFER TO DETAIL 20/A10.02 FOR FLOOR MATERIAL CHANGES
3. REFER TO REFLECTED CEILING PLAN FOR CEILING HEIGHTS OF INDIVIDUAL ROOMS
4. ALL INTERIOR FINISHES SHALL COMPLY WITH CBC CHAPTER 8, CBC SECTION 1103, 3.3 AND TITLE 19 CCR.
5. PATCH & REPAIR FLOOR AND CEILING TO MATCH EXISTING.

ROOM FINISH SCHEDULE - BLDG. 500

ROOM		FLOOR		BASE		WALLS 1				WALLS 2				WALLS 3				WALLS 4				CEILING		NOTES	NO
		MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL	FINISH		
NO	NAME	1	1	1	1	1	2	1	2	1	2	1	2	1	2	1	2	1	2	1	2	1	1		
501	BOYS	--	--	--	--	(E)CT	(E)PLAS	--	E	(E)CT	(E)PLAS	--	E	(E)CT	(E)PLAS	--	E	(E)CT	(E)PLAS	--	E	--	--	--	501
502	GIRLS	--	--	--	--	(E)CT	(E)PLAS	--	E	(E)CT	(E)PLAS	--	E	(E)CT	(E)PLAS	--	E	(E)CT	(E)PLAS	--	E	--	--	--	502
503	WOMEN	(E) CT	PF	(E) CT	PF	(E) CMU	--	E	(E) CT	(E) PLAS	--	E	(E) CT	(E) PLAS	--	E	(E) CT	(E) PLAS	--	E	(E) CT	(E) PLAS	E	--	503
504	MEN	(E) CT	PF	(E) CT	PF	(E) PLAS	--	E	(E) CT	(E) PLAS	--	E	(E) CT	(E) CMU	--	E	(E) CT	(E) PLAS	--	E	(E) CT	(E) PLAS	E	--	504
505	FACULTY LOUNGE	VCT	PF	TSB	PF	(E) CMU	--	E	--	(E) CMU	--	E	--	(E) CMU	(E) VCTP	E	--	(E) PLY	--	E	--	(E) ACT	PF	--	505
506	CLASSROOM	VCT	PF	TSB	PF	(E) CMU	--	E	--	(E) PLY	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	T&T	PF	--	506
507	CLASSROOM	VCT	PF	TSB	PF	(E) CMU	--	E	--	(E) CMU	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) PLY	(E) VCTP	E	(E) PF	T&T	PF	--	507
508	CLASSROOM	VCT	PF	TSB	PF	(E) CMU	--	E	--	(E) PLY	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	T&T	PF	--	508
509	CLASSROOM	VCT	PF	TSB	PF	(E) CMU	--	E	--	(E) PLY	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) PLY	(E) VCTP	E	(E) PF	T&T	PF	--	509
510	CLASSROOM	VCT	PF	TSB	PF	(E) CMU	--	E	--	(E) CMU	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) PLY	(E) VCTP	E	(E) PF	T&T	PF	--	510

1

ROOM FINISH SCHEDULE - BLDG. 600

ROOM		FLOOR		BASE		WALLS 1				WALLS 2				WALLS 3				WALLS 4				CEILING		NOTES	NO
		MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL	FINISH		
NO	NAME	1	1	1	1	1	2	1	2	1	2	1	2	1	2	1	2	1	2	1	2	1	1		
601	BOYS	(E) CT	PF	(E) CT	PF	(E) CMU	(E) PLAS	E	(E) CT	(E) CMU	--	E	(E) CT	(E) PLAS	--	E	(E) CT	(E) CMU	--	E	(E) CT	(E) PLAS	E	--	601
602	GIRLS	(E) CT	PF	(E) CT	PF	(E) PLAS	--	E	(E) CT	(E) PLAS	--	E	(E) CT	(E) CMU	(E) PLAS	E	(E) CT	(E) CMU	--	E	(E) CT	(E) PLAS	E	--	602
603	HEATER ROOM	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	No work req'd.	603
604	ATHLETIC STORAGE	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	No work req'd.	604
605	CUSTODIAL	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	No work req'd.	605
606	CLASSROOM	VCT	--	TSB	PF	(E) CMU	--	E	--	(E) PLY	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	T&T	PF	--	606
607	CLASSROOM	VCT	--	TSB	PF	(E) CMU	--	E	--	(E) CMU	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) PLY	(E) VCTP	E	(E) PF	T&T	PF	--	607
608	CLASSROOM	VCT	--	TSB	PF	(E) CMU	--	E	--	(E) PLY	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	T&T	PF	--	608
609	CLASSROOM	VCT	--	TSB	PF	(E) CMU	--	E	--	(E) PLY	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) PLY	(E) VCTP	E	(E) PF	T&T	PF	--	609
610	CLASSROOM	VCT	--	TSB	PF	(E) CMU	--	E	--	(E) CMU	(E) VCTP	E	(E) PF	(E) CMU	(E) VCTP	E	(E) PF	(E) PLY	(E) VCTP	E	(E) PF	T&T	PF	--	610

1

ROOM FINISH SCHEDULE - BLDG. 1000

ROOM		FLOOR		BASE		WALLS 1				WALLS 2				WALLS 3				WALLS 4				CEILING		NOTES	NO
		MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL		FINISH		MATERIAL	FINISH		
NO	NAME		1	1	1	1	2	1	2	1	2	1	2	1	2	1	2	1	2	1	2	1	1		
1001	ROOM	VCT	PF	TSB	PF	GYP (E)	--	E	--	GYP (E)	--	E	--	GYP (E)	--	E	--	GYP (E)	--	E	--	(E)ACT	E	--	1001
1002	CLASSROOM	VCT	PF	TSB	PF	GYP (E)	--	E	--	GYP (E)	--	E	--	GYP (E)	--	E	--	GYP (E)	--	E	--	(E)ACT	E	--	1002

1 1

bfgc Architecture

Bakersfield
5500 ming avenue, suite 450, bakersfield, ca 93309
661.836.4300 fax 661.836.4311

San Jose
150 south first st., suite 200
san jose, california 95113
408.924.0841
fax 408.924.0844

San Luis Obispo
4115 broad street, suite b-6
san luis obispo, ca 93401
805.546.0433
fax 805.546.0504

Oakland
350 frank ogawa plaza, suite 300
oakland, california 94612
510.891.0670
fax 510.891.0674

Principal Architects
david r. cartnal, f.a.i.a., C-6564
frank a. ghezzi, a.i.a., C-3132
mark engelien, a.i.a., C-8021
william r. tucolet, a.i.a., C-8702
dean a. tatsuno, a.i.a., C- 9190
bruce m. bigger, a.i.a., C-23134
brad henderson, a.i.a., C-10901
richard l. mello, a.i.a., C-18079

LICENSED ARCHITECT MARK ENGELIEN C-8021 STATE OF CALIFORNIA

rev. no:	rev. date:	revision:
1	5-17-07	OWNER REVISION

FILE NO: 15-6
IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT
APPL NO: 03-106664
AC____ FLS____ SS____
DATE 8-26-03

REVISED 5-17-07

MODERNIZATION

FOR

COLONEL HOWARD NICHOLS SCHOOL
3401 RENEGADE AVE.
BAKERSFIELD, CA. 93306

BAKERSFIELD CITY SCHOOL DISTRICT

BUILDING 500,600 & 1000 ROOM FINISH SCHEDULE

Version Date:

job no.	02-127
date	8-26-03
drawn by	DESAI
chk'd by	R. TROST
©copyright	2002

Version time:

A 5.12