AURORA

RELOCATABLE CLASSROOM BUILDING

24 x 40

(STOCKPILE)

ELITE MODULAR
EML # T.B.D.
BAKERSFIELD S.D.
RELOCATION PACKAGE FROM STOCKPILE TO SITE SPECIFIC FOR :
HORACE MANN : (X2) 24X40 L.H. DOOR
SN'S :19433-34 / 19469-70
~~HORT: (X4) 24X40 R.H. DOOR~~
~~SN'S :19449-50/19563-64/19955-56/19959-60~~

D.S.A.
REVISED
IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT OFFICE OF REGULATION SERVICES
DATE 3-10-12
AGENCY P. NIKLESON
PLAN CHECK EML 65834
DATE 4-3-12
AGENCY D. FIGUEROA
FIELD INSPECTION
CHECKED
REVISIONS

FIRE ALARM NOTES

NFPA 13- Automatic Sprinkler Systems,	1994 Edition
NFPA 14- Standpipes Systems,	1993 Edition
NFPA 17A- Wet Chemical Systems,	1990 Edition
NFPA 24- Private Fire Mains,	1992 Edition
(California Amended) NFPA 72- National Fire Alarm Codes,	1993 Edition
NFPA 253- Critical Radiant Flux of Floor Covering Systems,	1984 Edition
NFPA 2001- Clean Agent Fire Extinguishing Systems,	1994 Edition

APPLICABLE CODES

1995 Building Standards Administrative Code, Part 1, Title 24 C.C.R.
1995 California Building Code (CBC), Part 2, Title 24 C.C.R.; (1994 Uniform Building Code volumes 1-3 and 1995 California Amendments)
1995 California Electrical Code (CEC), Part 3, Title 24 C.C.R. (1993 National Electrical Code and 1996 California Amendments)
1995 California Mechanical Code (CMC), Part 4, Title 24 C.C.R., (1994 Uniform Mechanical Code and 1995 California Amendments)
1995 California Plumbing Code (CPC), Part 5, Title 24 C.C.R.; (1994 Uniform Plumbing Code and 1995 California Amendments)
1995 California Fire Code (CFC), Part 9, Title 24 C.C.R.; (1994 Uniform Fire Code and 1995 California Amendments)
1994 California Referenced Standards Code, Part 12, Title 24 C.C.R.
1990 Title 19, CCR, Public Safety, state Fire Marshal Regulations

BLDG. DATA (50 LBS STANDARD)

OCCUPANCY	E-3
TYPE OF CONSTRUCTION	V - NON RATED
WIND LOAD	70 m.p.h. EXPOSURE 'C'
FLOOR LIVE LOAD	50 lbs/sq. ft.
ROOF LIVE LOAD	20 lbs/sq. ft.
BUILDING DATA	960 sq. ft.
SYSTEM:	R16ID FRAME
MODULES:	TWO 12'x 40'
~~FOUNDATION: CONCRETE~~	
~~FOUNDATION: FLUSH W/ GRADE CONCRETE~~	

~~BLDG. DATA (50 PSF+20 LBS PARTITIONS OPTION)~~

OCCUPANCY	E-1
TYPE OF CONSTRUCTION	V - NON RATED
WIND LOAD	70 m.p.h. EXPOSURE 'C'
FLOOR LIVE LOAD	50 lbs/sq. ft. + 20 LBS. PARTITIONS
ROOF LIVE LOAD	20 lbs/sq. ft.
BUILDING DATA	960 sq. ft.
SYSTEM:	R16ID FRAME
MODULES:	TWO 12'x 40'
FOUNDATION:	WOOD
FOUNDATION:	CONCRETE
FOUNDATION:	FLUSH W/ GRADE CONCRETE

~~BLDG. DATA (100 PSF OPTION)~~

OCCUPANCY	E-1
TYPE OF CONSTRUCTION	V - NON RATED
WIND LOAD	70 m.p.h. EXPOSURE 'C'
FLOOR LIVE LOAD	100 lbs/sq. ft.
ROOF LIVE LOAD	20 lbs/sq. ft.
BUILDING DATA	960 sq. ft.
SYSTEM:	R16ID FRAME
MODULES:	TWO 12'x 40'
FOUNDATION:	WOOD
FOUNDATION:	CONCRETE
FOUNDATION:	FLUSH W/ GRADE CONCRETE

~~BLDG. DATA (125 PSF OPTION)~~

OCCUPANCY	E-1
TYPE OF CONSTRUCTION	V - NON RATED
WIND LOAD	70 m.p.h. EXPOSURE 'C'
FLOOR LIVE LOAD	125 lbs/sq. ft.
ROOF LIVE LOAD	20 lbs/sq. ft.
BUILDING DATA	960 sq. ft.
SYSTEM:	R16ID FRAME
MODULES:	TWO 12'x 40'
FOUNDATION:	WOOD
FOUNDATION:	CONCRETE
FOUNDATION:	FLUSH W/ GRADE CONCRETE

INDEX

0 COVER SHEET, SHEET INDEX, & BUILDING DATA
1 FLOOR PLAN, ROOF PLAN, BUILDING ELEVATIONS
2A FOUNDATION PLAN AND DETAILS (WOOD 50 LBS. LIVE LOAD)
~~2B FOUNDATION PLAN AND DETAILS (WOOD 50 LBS. LIVE LOAD + 20 LBS. PARTITIONS)~~
~~2C FOUNDATION PLAN AND DETAILS (WOOD 100 LBS. LIVE LOAD)~~
~~2D FOUNDATION PLAN AND DETAILS (WOOD 125 LBS. LIVE LOAD)~~
~~3 FOUNDATION PLAN AND DETAILS (CONC. 50 LB. L.L. ABOVE GRADE)~~
~~4 FOUNDATION PLAN AND DETAILS (CONC. 50 LB. L.L. + 20 LBS. PARTITIONS, ABOVE GRADE)~~
~~5 FOUNDATION PLAN AND DETAILS (CONC. 100 LB. L.L. ABOVE GRADE)~~
~~6 FOUNDATION PLAN AND DETAILS (CONC. 125 LB. L.L. ABOVE GRADE)~~
~~7 FOUNDATION PLAN AND DETAILS (CONC. 50 LB. L.L. FLUSH W/GRADE)~~
~~8 FOUNDATION PLAN AND DETAILS (CONC. 50 LB. L.L. + 20 LBS. PARTITIONS, FLUSH W/GRADE)~~
~~9 FOUNDATION PLAN AND DETAILS (CONC. 100 LB. L.L. FLUSH W/GRADE)~~
~~10 FOUNDATION PLAN AND DETAILS (CONC. 125 LB. L.L. FLUSH W/GRADE)~~
3 BUILDING SECTIONS AND WALL FRAMING
4 TYPICAL DETAILS
5 FLOOR FRAMING, ROOF FRAMING & STRUCTURAL ELEVATIONS
5.1 STEEL TRUSS SECTION AND DETAILS
~~6 STRUCTURAL DETAILS (BUILT-UP ROOFING)~~
6S STRUCTURAL DETAILS (22 GA. ROOFING)
~~6A STRUCTURAL DETAILS (26 GA. ROOFING)~~
7 REFLECTED CEILING PLAN & DETAILS
8 ELECTRICAL POWER & LIGHTING PLAN AND PANEL SCHEDULE
9 SPECIFICATIONS & INTERIOR & EXTERIOR & FINISH SCHEDULES
R1 ROOF PLAN AND DETAILS (METAL DECK)
~~T-1 RAMP PLAN AND DETAILS (HANDRAIL)~~
M1 AIR CONDITIONING PLAN.

INDEX FOR ALTERNATE RESTROOM FLOOR PLAN

1. FLOOR, ROOF PLAN, ELEV. & ELEVATIONS (RESTROOM FLOOR PLAN)
7 REFLECTED CEILING PLAN & DETAILS (RESTROOM FLOOR PLAN)
8 ELEC. & LIGHTING PLAN (RESTROOM FLOOR PLAN)

NOTE: THESE SHEET ARE TO BE USE IF THE INTENT IS FOR A RESTROOM ALL OTHER SHEET STILL APPLY

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT
03 11 0812
AGENCY
Date SEP 06 2011

AURORA MODULAR INDUSTRIES
18333 Kramer Ave., Riverside, CA. 92504
Phone (909) 780-7788
Fax (909) 780-0555
RELOCATABLE BUILDING FOR:
WILLIAMS/SCOTSMAN GROUP

COVER SHEET, SHEET INDEX, BUILDING DATA

SHEET 0

3767

Lost either way, we'll come up with it.