



- ### KEY NOTES
- 1 TYP. INTERIOR FINISH (SEE FINISH SCHEDULE.)
 - 2 TYP. EXTERIOR FINISH
 - 3 1/2" GYPSUM BOARD BACKING W/ 7d COOLER NAILS @ MAX 7" O.C. TYP. • EA. STUD
 - 4 2X4 STUD TYP. @ 16" O.C. MAX.
 - 5 WIRE MESH CLOSURE. ATTACH TO COLUMN W/#10 STMS @ 12" O.C.
 - 6 NOT USED
 - 7 TUBE STEEL COLUMN (SEE STRUCTURAL)
 - 8 SEALANT TYP. (SEE SPECS.)
 - 9 #10 S.T.S.M.S. @ MAX. 24" O.C. (ALT. HILT. 0.145 SHOT PIN) 2X FILLER TO COLUMN
 - 10 VINYL CLOSURE
 - 11 MODULE JOINT
 - 12 16d @ 24" O.C. FACE NAIL OR 16d @ 12" O.C. TOE NAIL (SEE SHT. S5.2)
 - 13 FLOOR BEAM (SEE STRUCTURAL)
 - 14 PRESSED STEEL FRAME (K.D. TYPE SEE A5.0)
 - 15 ALUMINUM THRESHOLD (SEE HARDWARE SCHEDULE)
 - 16 FINISH LANDING SEE FLOOR PLAN & FOUNDATION FOR TYPE AND FINISH
 - 17 DOOR BOTTOM (SEE HARDWARE SCHEDULE)
 - 18 (2) 2X4 KING STUD NAILING SCHEDULE (SEE SHT. S5.1 FOR NAILING)
 - 19 2X4 TRIMMER (SEE SHT. S5.1 NAILING SCHEDULE FOR NAILING)
 - 20 CORNER MOLDING
 - 21 1X4 WOOD TRIM W/6d ELECTRO GALV. @ 12" O.C.
 - 22 2-2X4 SILL PLATE W/16d @ 16" O.C.
 - 23 INSULATION (SEE SPECS. FOR SIZE AND TYPE)
 - 24 FINISH FLOORING (SEE FINISH SCHEDULE SHT. A5.0)
 - 25 2X4 JAMB STUDS (SEE SHT. S5.1 DETAILS FOR NUMBER OF STUDS REQUIRED AND NAILING SCHEDULE FOR NAILING)
 - 26 WINDOW GLAZING (SEE WINDOW SCHEDULE SHEET A5.0)
 - 27 2 X 6 LET IN (SEE WALL FRAMING SHT. S5.0)
 - 28 ALUMINUM WINDOW FRAME WITH NAIL-ON FINISH. INSTALL W/MIN. 3" BLDG. PAPER BTWN. FIN. AND FRAMING. INSTALL WITH 6d @ MAX 24" O.C.
 - 29 16d BOX STAGGERED @ MAX 24" O.C.
 - 30 HEADER (SEE SHT. S5.1 WALL FRAMING DETAILS)
 - 31 DOOR (SEE DOOR SCHED.)
 - 32 6-3/8" @ X 2" GALV. LAG SCREWS
 - 33 L 1 1/2"x1 1/2"x1/8"x18" LONG (BY HVAC MFR) ATTACHED TO A/C W/4-#10 SELF TAPPING SHEET METAL SCREWS & ATTACH TO WALL W/3" @ X 2" GALV. LAG SCREWS.
 - 34 SIDE OF HVAC UNIT (SEE SHEET M-1)
 - 35 (3) 2X4 W/ PLYWOOD SPACER- BUILT- UP POST. 6d @ O.C. STAGGERED SPACER TO FIRST 2 X 4. 16 d @ 12" O.C. 2 nd 2 X 4. 12d @ 12" O.C. STAGGERED Jrd. 2 x 4. ALTERNATE USE 4 X 4 POST.
 - 36 11GA X 24" STEEL SUPPORT BRACKET.
 - 37 DRIP FLASH
 - 38 6d EN @ 6" O.C.

NOTES

1. EN 6d ELECTRO GALV. @ 6" O.C.
2. FN 6d ELECTRO GALV. @ 12" O.C.
3. SEE SHEET S5.1 FOR TYPICAL WALL FRAMING NAILING

REVISIONS	Electrical Engineer's Seal	Mechanical Engineer's Seal	Structural Engineer's Seal	Architect's Seal	Division of the State Architect

MODTECH INC.
 2830 BARRETT AVENUE
 PERRIS, CALIF. 92572
 PH (909) 943-4014
 FAX (909) 940-0427

PROJECT NUMBER: 2986

DIV. OF THE STATE ARCHITECT
 OFFICE OF REGULATION SERVICES
 PC 208
 JUN 25 1997

IDENTIFICATION STAMP
 DIV. OF THE STATE ARCHITECT
 OFFICE OF REGULATION SERVICES
 AC/FLS/SS/TN
 DATE JAN 07 1999

ARCHITECTURAL DETAILS

STKP-42
 11/29/98

drawn by: 4012-088
 checked by: 05 JAN 99
 project no:

A6.0