




LANDING FRAME 12




RAMP FRAME 7




SILL PLAN FOR RAMP AND LANDING 3/8" 1




LANDING ELEVATION 13




RAMP ELEVATION 8




RAMP AND LANDING AT BUILDING 3/8" 2




LONG. SECTION @ LANDING 14



LONGITUDINAL SECTION @ RAMP 9




RAMP EXTENSION TO RAMP 5




GUARD RAIL EXTENSION 3

- KEY NOTES**
- TS 2" x 2" x 14ga
 - TS 1 1/2" x 1 1/2" x 14ga (Fy = 39KSI)
 - TS 1" x 1" x 16ga WHEELCHAIR GUIDE
 - 2 x 6 FT SILL PLATE
 - 8" x 10ga CONT. PLATE W/ 1/4" X 2" TEK SCREWS @ 9" OC INTO WOOD OR FOUND. BLOCKS OR #14 x 2" TEK SCREWS INTO STEEL @ 9" OC
 - 8" x 12" x 10ga PLATE W/ 2-1/4" x 3" LAGS TO STRUCTURAL FRAME OF BUILDING
 - 3" x 1" x 3'-0" x 10ga BENT PLATE
 - 2" x 4" x 12ga BASE PLATE W/ 2-1/4" x 1" LAGS
 - 8" x 10" x 12ga BASE PLATE @ RAMP TOE
 - LINE OF RAMP/LANDING ABOVE
 - LOWER LANDING BY DISTRICT
 - SHORTING: PLYWOOD TO MATCH BUILDING SIDING. BLOCK ALL EDGES. ATTACH W/ 8d @ 8" OC EDGES AND 12" OC FIELD. AT EDGE CONNECTION TO T.S. USE #14 x 2" TEK SCREWS @ 8" OC
 - 12ga METAL DECK: NON-SLIP SURFACE. DESIGN COEFFICIENT OF FRICTION GREATER THAN 6%. MAINTAINABLE FOR 1 YR. RAMP EXTENSION FRAME.
 - EXISTING BUILDING.
 - RAMP BY MODTECH
 - FLUSH TRANSITION
 - NOTCH BOTTOM PLATE (MUD SILL) AS REQUIRED TO CLEAR RAMP TOE. MAX NOTCH 1 1/2" x 4'-0" LONG.
 - TS 1" x 1" x 16ga



LANDING TO RAMP 4



LANDING TO RAMP 4

- NOTES**
- RAMPS: RAMPS SHALL NOT SLOPE MORE THAN 1" IN 12"
 - HANDRAILS: HANDRAILS AT BOTH SIDES OF RAMP AT 34" HT.
 - SURFACE: LANDING & RAMP TO HAVE NON SLIP SURFACE AMCOR GRIP II AS MANUFACTURED BY AMERICAN CHEMICAL COMPANY (OR EQUAL)
 - GROUNDING: PROVIDE GROUNDING OF RAMP TO BLDG FRAME W/ #8 CU TO BOTH GROUND LUGS.
 - ARCHITECT SITE / RAMP / LANDING PLANNING: DUE TO VARYING SITE CONDITIONS THE MAXIMUM HEIGHT OF FINISH FLOOR FROM GRADE IS 28" THEREFORE IT IS POSSIBLE THAT THE ACCESS RAMP ATTACHED TO THE BUILDING SHOULD BE 28'-0" AT A SLOPE OF 1:12 ARCHITECT MUST TAKE INTO ACCOUNT THAT THE RAMP SUPPLIED BY MODTECH INC. IS 11'-0" AT A SLOPE OF 1:12 THEREFORE THE ARCHITECT WILL HAVE TO DESIGN AND PROVIDE SUFFICIENT DETAILS OF RAMP EXTENSIONS AND BOTTOM LANDING DEPENDING ON PARTICULAR SITE CONDITIONS. IN NO WAY IS MODTECH INC. RESPONSIBLE FOR ANY RAMP EXTENSION EXCEEDING THE ORIGINAL PLAN AS SHOWN ON SHEET R-1.
 - ALL 1 1/4" AND 1 1/2" TUBE STEEL TO BE OF ASTM A500 GRADE A STEEL (Fy = 39 KSI)

REVISIONS

1		
2		
3		
4		
5		
6		

Professional seals for Electrical, Mechanical, Structural, and Architect. Includes Modtech Inc. logo and identification stamp.

MODTECH INC.
 2830 BARRETT AVENUE
 PERRIS, CALIF. 92572
 PH. (909) 943-4014
 FAX. (909) 940-0427

Job Number: PC 266
 © MODTECH, INC. 1997
 2900 4012-083
STKP-37
RAMP / LANDING
R1.0