

DOOR SCHEDULE

DOORS						FRAMES						NOTE NO.
DOOR NUMBER	FRAME OPENING SIZE	MATERIAL	TYPE	FIRE RATING	HARDWARE SET NO.	QUANTITY	MATERIAL	HEAD DETAIL	JAMB DETAIL	SILL DETAIL	JAMB THROAT	
1	3'-0" X 6'-8"	HM	A	NA	1	1	HM	7/A4.03	8/A4.03	1/A4.03	5-1/8"	

HM - HOLLOW METAL
 AL - ALUMINUM
 SST - STAINLESS STEEL
 STL - STEEL
 WWF - WINDOW WALL FRAME
 SC - SOLID CORE WOOD
 HC - HOLLOW CORE WOOD
 SCL - SOLID CORE WOOD LEGACY

WINDOW SCHEDULE

AMT.	TYPE	WIDTH	HEIGHT	FINISH	WIN. NO.	GLASS TYPE
2	1	8'-0"	4'-0"	ANODIZED	A	7/32" MIN, SOLAR GRAY 46%, DUAL GLAZE

AMOUNT: 2
 TYPE: 1
 WIDTH: 8'-0"
 HEIGHT: 4'-0"
 FINISH: ANODIZED
 WINDOW NUMBER: A
 GLASS TYPE: 7/32" MIN, SOLAR GRAY 46%, DUAL GLAZE

ROOM FINISH SCHEDULE


ROOM NUMBER	ROOM NAME	FLOOR	BASE	FINISHES				CEILING	CEILING HEIGHT	REMARKS
				FRONT WALLS	LEFT WALLS	REAR WALLS	RIGHT WALLS			
1	CLASSROOM	A	D	F	F	F	F	L	8'-6"	

A - CARPET PER STATE OF CALIF SPEC 7220-51E-04 COMPLYING WITH GROUP 1, TYPE A OR TYPE B, CLASS 2, DENSITY 4600, DIRECT GLUE DOWN WITH 4" TOPSET BASE.
 B - VINYL SHEET FLOORING
 C - SELF COVE BASE - 6"
 D - 4" BURKE
 E - 6" BRIGANTINE OR SANDOVAL
 F - 1/2" VINYL TACKBOARD CLASS-1 OVER 1/2" GYP. BOARD BACKING
 G - 1/2" W.R. GYP. BOARD TAPE TEXTURE WITH PAINTED FINISH
 H - 3/8" W.R. GYP. BOARD TAPE TEXTURE WITH PAINTED FINISH
 I - 1/2" GYP. BOARD TAPE TEXTURE WITH PAINTED FINISH
 J - 3/8" GYP. BOARD TAPE TEXTURE WITH PAINTED FINISH
 K - 1/8" MARLITE OVER 1/2" W.R. GYP. BOARD
 L - ACCOUSTICAL LAY IN GRID CEILING PANELS (SEE SPECIFICATIONS)
 M - 3/32" FRP OVER 1/2" WR GYP. BOARD


NOTES

1. ALL FINISHES SHALL COMPLY WITH C.B.C. CHAPTERS 3,6,7,8, & 10 & C.F.C. & TITLE 19 C.C.R.
 2. FOR DOOR AND DOOR FRAME DATA SEE SPECIFICATIONS ON SHEET AB.0.

DOOR ELEVATIONS



WINDOW ELEVATIONS



DOOR NOTES

- DOOR HANDLES FOR LOCKSETS TO BE CENTERED @ 36" AFF & DEADBOLTS @ 44" AFF.
- HARDWARE TO BE OPENABLE FROM THE INSIDE WITHOUT ANY SPECIAL KNOWLEDGE OR EFFORT. LEVERS TO RETURN TO WITHIN 1/2" OF DOOR.
- ALL DOORS SHALL BE 1-3/4" THICK UNO
- DOUBLE LETTERS IN SCHEDULE, INDICATES A PAIR OF DOORS.
- SAFETY GLASS, CLEAR
- WIRE GLASS
- UNDERCUT DOOR
- FIXED LOUVER
- FUSIBLE LINK LOUVER
- VISION PANEL
- CLOSURE SHALL BE SET FOR MAXIMUM OPENING PRESSURE OF 5 LBS ON ALL DOORS

WINDOW NOTES

- 8040 XOX ANODIZED ALUMINUM GLAZING; EXTERIOR LITE 3/16" MIN. TEMPERED GLASS OF SOLAR GRAY WITH A LITE TRANSMISSION FACTOR OF 46%. 1/4" ALUMINUM SPACER. INTERIOR LITE - 1/8" MIN. CLEAR TEMPERED. ALL OPERABLE SASH SHALL HAVE ALUMINUM SCREENS.


FINISH NOTES

- SUB-FLOOR PREP:
 PREPARATION FOR SUB FLOOR TO ACCEPT FINISH FLOORING IS BY FLOORING CONTRACTOR. PLYWOOD SUB FLOOR IS 2.4.1 PLYWOOD. OUTER PLY IS PLUGGED AND TOUCH SANDED, ANY DEFORMITIES DUE TO STANDARD CONSTRUCTION PRACTICES SHALL BE FILLED AND SANDED BY FLOORING CONTRACTOR. THE JOINT AT THE MODULE JOINING SHALL NOT BE LARGER THAN 1/8" AND SHALL BE FILLED AND SANDED BY FLOORING CONTRACTOR.


HARDWARE SCHEDULE

- HARDWARE SET #1**
- LOCKSET - SCHLAGE D70PD, WITH RHODES LEVER, OR EQUAL
 - BUTTS - 1-1/2 PAIR HAGER 1191 BB 4-1/2 x 4-1/2 NRP 26D OR EQUAL
 - CLOSER - NORTON 8500 DA / LCN 480 OR EQUAL
 - THRESHOLD - PEMCO 271A OR EQUAL
 - DOOR BOTTOM - PEMCO 216AV OR EQUAL
 - WEATHERSTRIP - PEMCO 299AV OR EQUAL
 - DOOR STOP - QUALITY #44 OR EQUAL
- HARDWARE SET #2**
- LOCKSET - SCHLAGE D53PD, WITH RHODES LEVER, OR EQUAL
 - BUTTS - 1-1/2 PAIR HAGER BB1279 4-1/2 x 4-1/2 26D OR EQUAL

ACCESSIBILITY SIGNAGE (BY DISTRICT)



TOILET ROOM SIGNAGE (BY DISTRICT)



AGENCY TRACKING NO. 63321-154
 FILE NO. 15-6

IDENTIFICATION STAMP
 DIV. OF THE STATE ARCHITECT
 OFFICE OF REGULATION SERVICES
 03-117035
 AC 10 FLS - SS B1
 DATE 0/28/2016



IDENTIFICATION STAMP
 DIV. OF THE STATE ARCHITECT
 OFFICE OF REGULATION SERVICES
 04 105455
 AC 16 FLS - SS 116
 DATE JUL 17 2003

~~IDENTIFICATION STAMP
 DIV. OF THE STATE ARCHITECT
 OFFICE OF REGULATION SERVICES
 JUL 10 2003~~

REVISIONS

NO.	DESCRIPTION	DATE

Electrical Engineer's Seal
 Mechanical Engineer's Seal
 Structural-Engineer's Seal
 Architect's Seal



MODTECH INC.
 2830 BARRETT AVENUE
 PERRIS, CALIF. 92572
 PH (909) 943-4014
 FAX (909) 940-0427

PROJECT NUMBER: 4736
 WILLIAM SCOTTSMAN
 © MODTECH, INC. 1999

SCHEDULE SHEET

DRAWN BY: GL
 DATE: 07/07/03
 CHECKED BY:
 DATE:
 MODTECH Index No.

A6.02