



**SECTION A-A**

1/2"=1'-0"

KEY NOTES 8712 SEC

NOTES LISTED IN THIS COLUMN WHICH ARE NOT INDICATED ON THIS SHEET SHALL BE DISREGARDED. COMPLETE PATCH AND REPAIR OF AREAS AND ADJACENT AREAS WHERE REMOVAL, DEMOLITION OR MODIFICATIONS ARE MADE ARE A PART OF THIS WORK. FIELD VERIFICATION FOR ACTUAL EXISTING CONDITIONS PRIOR TO BIDDING, FABRICATION, INSTALLATION OR CONSTRUCTION IS A PART OF THIS WORK. NOTES ARE TYPICAL UNLESS OTHERWISE INDICATED.

LEGEND

(N) = NEW; AS S.D.S.S. = AS SHOWN, DETAILED, SCHEDULED, &/OR SPECIFIED.  
 (E) = EXISTING;  
 (D) = DEMOLITION;

- 1D. (E) SLAB TO REMAIN.
- 2D. (E) 2 X 6 STUDS @ 16" O.C. W/INT. PLYWD AND EXT. PLASTER TO REMAIN.
- 3D. (E) 10 WF 21 COLUMN TO REMAIN.
- 4D. (E) 12 WF 27 TO REMAIN.
- 5D. (E) 2 X 4 LAMINATED ROOF DECKING TO REMAIN.
- 6D. (E) 1 1/2" RIGID INSULATION/ASPHALT SHINGLES TO REMAIN. (DEMO AND REPLACE IN KIND AS REQUIRED AT MECHANICAL DEMO.)
- 7D. (E) GLAZING SYSTEM TO REMAIN.
- 8D. (E) GLAZING SYSTEM TO BE REMOVED.
- 9D. (E) ACOUSTIC TILE/STRIPPING TO REMAIN. DEMO AS REQUIRED FOR (N) T-BAR CEILING. REPLACE, CLEAN AND REPAINT WHERE EXPOSED @ LIGHTWELLS.
- 10D. (E) DARKENING DRAPES AND APPURTENANT ITEMS TO BE REMOVED.

NEW

- 1. (N) PROVIDE & INSTALL R-30 LAY-IN BATT INSULATION AS S.D.S.S.
- 2. (N) PROVIDE & INSTALL (N) SUSPENDED T-BAR CEILING W/2 X 4 GRID & ACOUSTIC PANELS AS S.D.S.S.
- 3. (N) PROVIDE & INSTALL (N) DARKENING DRAPE & APPURTENANT ITEMS AS S.D.S.S. (EXISTING TRACK TO REMAIN AND BE REUSED.)

date  
6/23/89  
revisions

**MUNSEY SCHOOL MODERNIZATION**  
 BAKERSFIELD CITY SCHOOL DISTRICT  
 BAKERSFIELD, CALIFORNIA

APPROVED  
 PROJECT MANAGER  
 OFFICE OF THE SUPERVISOR  
 FEB 27 1989  
 Structural Safety Section

ONLY  
 FEB 27 1989

TITLE 24 & 1319 USE

7  
 5244 7/1/80

*Gregory J. ...*  
 architects • planners

*Kendrick Design Group*

2115 19th street • bakersfield, ca 93301 • (805) 322-1863

job number  
**8712**

sheet number  
**A-18**