ROOM FINISH SCHEDULE

ROOM		FLOOR			BASE			NORTH WALL				EAST WALL				SOUTH WALL				WEST WALL				CEILING			CASEWORK				DOORS		REMARKS	no
								wall		trim		wall		trim		wall		trim		wall		trim					top		face					
no	name	mat	fin		mat	fin	SEE NOTES	mat	fin	mat	fin	mat	fin	mat	fin	mat	fin	mat	fin	mat	fin	mat	fin	ht	mat	fin	mat	fin	mat	fin	mat	fin		
901	STAFF				4"TSB	INT	4																											901
902	STAFF.				4"TSB	INT	4																											902
903	PHYSICAL EDUCATION # 24	VCT	INT	B,T	4"C.B. 4"T.S.	INT	4																		*							* REPAIR ALL DAMAGED AREAS	903
904	PHYSICAL EDUCATION # 23	VCT	INT	B	4"TSB	INT	4																		*							* REPAIR ALL DAMAGED AREAS	904

A.T. = ACOUSTIC TILE
A.W.C. = ACOUSTIC WALL COVERING
AGG. = AGGREGATE
AL. = ALUMINUM
ASB. = ASBESTOS

BD. = BOARD
BLK. = BLOCK

C. = CARPET
CHB = CHALKBOARD

CBG = CARPET EDGE STRIP
CEM. = CEMENT
C.P. = CEMENT PAINT
CER. = CERAMIC
C.T. = CERAMIC TILE
CLG. = CEILING
CONC. = CONCRETE
CV. = COVED
CPB = CARPET BASE

DW. = DRYWALL

(E) = EXISTING
E. = ENAMEL

EXP.ST = EXPOSED STRUCTURE

FIN. = FINISH

G.B. = GYPSUM BOARD
GYP. = GYPSUM
GL. = GLASS

H.M. = HOLLOW METAL
H.S. = HARDNER/SEALER
HT. = HEIGHT

INT. = INTEGRAL

L.P. = LAMINATED PLASTIC

MAT. = MATERIAL
M.CB. = METAL CHALKBOARD
M.U. = MASONRY UNIT

NAT. = NATURAL
NO. = NUMBER

PF = PREFINISHED
PL. = PLASTER
PLYWD. = PLYWOOD
P.V.A. = POLY-VINYL ACETATE
Q.T. = QUARRY TILE

RES. = RESILIENT
RWD. = REDWOOD

S.M. = SHEET METAL
SHT. = SHEET
SHT.V. = SHEET VINYL
STL. = STEEL

TR = TRANSPARENT
T.S. = TROWEL SMOOTH
TX. = TEXTURE
T. & T. = T-BAR ACOUSTIC TILE
TER. = TERRAZZO
TB. = TACKBOARD
T.M.E. = TO MATCH EXISTING
TS.B. = TOPSET BASE

V.C.T. = VINYL COMP. TILE
V.C.TB. = VINYL COVERED TACKBOARD
V.W.C. = VINYL WALL COVERING

W.C. = WALL COVERING
WD. = WOOD
WP. = WATERPROOF
WSCT. = WAINSCOT

1) UNLESS OTHERWISE NOTED, BLANK BOXES INDICATE EXISTING SURFACES, FINISHES, ETC. TO REMAIN.
2) PATCH & REPAIR ALL DAMAGED AREAS W/ MATCHING MATERIALS, TEXTURE & COLORS, PAINT WHERE INDICATED.
3) INFILL EXIST'G OPENS AS INDICATED IN PLANS OR INTERIOR/EXTERIOR ELEVATIONS. PATCH & MATCH (N) AREA & ADJACENT SURFACES AS REQ'D. PAINT AS INDICATED.
4) REMOVE EXIST'G BASE, AND INSTALL NEW BASE AS INDICATED
5) REMOVE EXIST'G VCT, PREPARE SURFACE AND INSTALL NEW FLOORING
6) REMOVE ANY LOOSE OR DAMAGED VCT, REPAIR W/ NEW VCT, AND INSTALL NEW FLOORING
7) REMOVE EXIST'G FLOORING, PREPARE NEW SURFACE FOR NEW FLOORING AS INDICATED.
8) REMOVE PORTIONS OF EXISTING WALL FOR (N) OPENS AS INDICATED ON PLANS/ELEVATIONS. INSTALL (N) WINDOW/DOOR FRAME AS INDICATED ON WINDOW/DOOR SCHEDULE.
9) REMOVE (E) DOOR & REPLACE W/ NEW. PATCH ADJACENT SURFACES AS REQ'D.
10) U.O.N. ALL WALL SURFACES AROUND SINK AREA SHALL RECEIVE ENAMEL PAINT. REFER TO INTERIOR ELEVATIONS.
11) ALL PLASTER @ TOILETS SHALL BE PORTLAND CEMENT.

Key Plan

approved REVISED 1 OCT 1 '97 D.K.

C-1128
C-3269
C-3132
C-6564K

DAVID K. GEORGE

bigger frapwell ghezzi cartnal
architects / planners
7 south real road 661 4646
bakersfield california 93309

ROOM FINISH SCHEDULE

BLAIR LEARNING CENTER RECONSTRUCTION

900 belle terrace, bakersfield, california

job 85-102

date 3 OCT 1986

sheet A6