CHECK AND VERIFY ALL DIMENSIONS BEFORE PROCEEDING WITH THE WORK. REPORT ANY DISCREPANCIES TO ARCHITECT.

COUNTY OF KERN
OFFICE OF SUPERINTENDENT OF SCHOOLS
JESSE D. STOCKTON — SUPERINTENDENT

APPROVED

DATE

STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF ARCHITECTURE

APPLICATION NO. 8238 — APPROVED MAY 18 19[illegible]

STATE OF CALIFORNIA DEPARTMENT OF PUBLIC WORKS
DIVISION OF ARCHITECTURE
APPROVED
DATE 3/1/51

BAKERSFIELD CITY SCHOOLS
1400 K ST. BAKERSFIELD, CALIFORNIA
BOARD OF EDUCATION

JUNIOR HIGH SCHOOL
BAKERSFIELD CITY SCHOOL DISTRICT
BELLE TERRACE & P STREETS
BAKERSFIELD — CALIFORNIA

JOB NO. 50-23 — C-335

ERNEST L. McCOY · A·I·A · ARCHITECT
129 HAY BLDG. — 1612 - 19th ST.
BAKERSFIELD — CALIFORNIA

DRAWN BY AJC — CHK'D — DATE 3/1/51

ROOM FINISH SCHEDULE

UNIT NUMBER	ROOM NUMBER	ROOM NAME	CEILING HEIGHT	FLOOR MATERIAL	FLOOR FINISH	BASE MATERIAL	BASE FINISH	WALLS MATERIAL	WALLS FINISH	WAINSCOT MATERIAL	WAINSCOT HEIGHT	MISCELLANEOUS
UNIT A	1	SOC STUDIES	VARIES	CONCRETE SLAB	CEMENT TROWELED SMOOTH NATURAL FINISH	WOOD	COLOR AS SELECTED	PLASTER	PAINTED COLOR AS SELECTED			
	2	" " "	"	"	"	"	"	"	"			
	3	" " "	"	"	"	"	"	"	"			
	4	" " "	"	"	"	"	"	"	"			
	5	" " "	"	"	"	"	"	"	"			
	6	TEACHERS LOUNGE	"	"	"	"	"	"	"			
	7	TOILET ROOM	10'-0"	"	"	"	"	"	"			
UNIT B	3	ENGLISH	VARIES	CEMENT COVE RUBBER CERAMIC TILE WOOD RUBBER COVE	PAINTED NATURAL COLORS AS SELECTED ROK-TITE	ASPHALT TILE CERAMIC TILE MAPLE OREGON PINE T & G OAK CORK TILE END GRAIN BLOCK COLOR AS SELECTED		METAL LATH NO. 3G SAND FIN. PLAS CEMENT PLASTER INTEGRAL TROWELED SAN EXPOSED CONCRETE BY FORM & BRICK CERAMIC TILE FIRE BRICK FIRE TILE PLAS. PACKING (SEE SPECS.)	PAINTED NATURAL COLORS AS SELECTED ROK-TITE			
	9	"	"									
	10	"	"									
	11	"	"									
	12	"	"									
	13	CUSTODIAN	10'-0"									
	13A	TRANSF. VAULT	9'-6"									
UNIT C	14	BOOK STORAGE	10'-0"									
	15	SUPPLIES STORAGE	"									
	16	TOILET ROOM	"									
	17	PRINCIPAL	"									
	18	WORK AREA	"									
	19	VESTIBULE	"									
	20	COUNSELOR	"									
	21	"	"									
	22	BOYS HEALTH RM	"									
	23	VEST BULE	"									
	24	BOYS TOILET	"									
	25	GIRLS TOILET	"									
	26	GIRLS HEALTH RM	"									
	27	GIRLS TOILET	"									
	28	BOYS TOILET	"									
UNIT D	29	LIBRARY	VARIES									
	30	CONTROL	"									
	31	FILING ROOM	10'-0"									
	32	CLOTHING	VARIES									
	33	FOODS	"									
	34	DINING	10'-0"									
	35	STORAGE	"									
UNIT E	37	VOCAL MUSIC	14'-0"									
	38	OFFICE	10'-0"									
	39	"	"									
	40	UNIFORM STO	"									
	41	INSTRUMENT STO	"									
	42	INSTRUMENT MUSIC	14'-0"									
UNIT F	44	MATHEMATICS	VARIES									
	45	"	"									
	46	"	"									
	47	"	"									
	48	"	"									
	49	GIRLS TOILET	10'-0"									
	50	BOYS TOILET	"									
UNIT G	51	BOYS PHYS ED	VARIES									
	52	GIRLS PHYS ED	"									
	53	ATHLETIC STORAGE	10'-0"									
	53A	CUSTODIAN	"									
UNIT A	54	SCIENCE	14'-0"									
	55	STOR RM	10'-0"									
	56	DINING ROOM	14'-0"									
	57	DISHWASHING	10'-0"									
	58	SERV NO	"									
	59	KITCHEN	"									

REFER TO INTERIOR ELEVATIONS & CEILING PLAN FOR EXTENT OF FINISH

7'-0" HIGH PLYWOOD WAINSCOT

REFER TO INTERIOR ELEVATIONS & CEILING PLAN FOR EXTENT OF FINISH

7'-3⅝" HIGH CERAMIC TILE WAINSCOT

7'-3⅝" HIGH CERAMIC TILE WAINSCOT

7'-3⅝" HIGH CERAMIC TILE WAINSCOT

7'-3⅝" HIGH CERAMIC TILE WAINSCOT SHOWER CEILING TO BE CEMENT PLASTER

" " " " " " " " " "

7'-3⅝" HIGH CERAMIC TILE WAINSCOT

7'-3⅝" HIGH CERAMIC TILE WAINSCOT

SEE ROOM ELEVATIONS & DETAILS FOR WOOD & GLASS PARTITIONS