ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR MATERIAL	FLOOR FINISH	BASE MATERIAL	BASE FINISH	WALL MATERIAL	WALL FINISH	CEILING MATERIAL	CEILING FINISH	TRIM MATERIAL	TRIM FINISH	MISCELLANEOUS	REMARKS
1	CLASSROOM	4"CONC. SLAB	ASPHALT TILE	WOOD- SOFT PINE	PAINTED	NO.30 SAND FIN. PLAS.-ROCK LATH	PAINTED	FIBRE BOARD	NATURAL FIN.	WOOD- SOFT PINE	PAINTED	HEATER RECESS TO HAVE METAL LATH AND PLASTER WALLS AND CEILINGS.	
2	" "	" "	" "	" "	"	" "	"	" "	" "	" "	"	"	
3	" "	" "	" "	" "	"	" "	"	" "	" "	" "	"	"	
4	" "	" "	" "	" "	"	" "	"	" "	" "	" "	"	"	
5	" "	" "	" "	" "	"	" "	"	" "	" "	" "	"	"	
6	CUSTODIAN ROOM	" "	TROWELED SMOOTH	" "	"	" "	"	NO.30 SAND FIN. PLAS.-MET. LATH	PAINTED	" "	"		
7	ATHLETIC SUPPLY	" "	ASPHALT TILE	" "	"	" "	"	FIBRE BOARD	NATURAL FIN.	" "	"		
8	BOYS TOILET	" "	TROWELED SMOOTH	CEMENT	COLORED	CEM. PLAS. TROW. SMOOTH-MET. LATH	"	H.W. PLASTER - MET. LATH	SAND FIN. PAINTED	" "	"		
9	GIRLS TOILET	" "	" "	"	"	" "	"	" "	"	" "	"	HEATER RECESS TO HAVE METAL LATH AND PLASTER WALLS AND CEILINGS.	
10	CLASSROOM	" "	ASPHALT TILE	WOOD	PAINTED	NO.30 SAND FIN. PLAS.-ROCK LATH	"	FIBRE BOARD	NATURAL FIN.	" "	"		
11	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
12	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
13	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
14	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
15	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
16	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
17	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
18	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
19	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
20	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
21	CUSTODIAN ROOM	" "	TROWELED SMOOTH	" "	"	" "	"	NO.30 SAND FIN. PLAS.-MET. LATH	PAINTED	" "	"		
22	BOYS TOILET	" "	" "	CEMENT	COLORED	CEM. PLAS. TROW SMOOTH-MET. LATH	"	H.W. PLASTER "	SAND FIN. PAINTED	" "	"		
23	GIRLS TOILET	" "	" "	"	"	" "	"	" "	"	" "	"		
24	TEACHERS LOUNGE	" "	ASPHALT TILE	WOOD	PAINTED	NO.30 SAND FIN. PLAS.-ROCK LATH	"	FIBRE BOARD	NATURAL FIN.	" "	"		
25	CUSTODIAN ROOM	" "	TROWELED SMOOTH	" "	"	" "	"	NO.30 SAND FIN. PLAS.-MET. LATH	PAINTED	" "	"		
26	TEACHERS TOILET	" "	ASPHALT TILE	" "	"	CEM. PLAS. TROW. SMOOTH-MET. LATH	"	H.W. PLASTER "	SAND FIN. PAINTED	" "	"		
27	TEACHERS WORK ROOM	" "	" "	" "	"	NO.30 SAND FIN. PLAS.-ROCK LATH	"	FIBRE BOARD	NATURAL FIN.	" "	"		
28	CLASSROOM	" "	" "	" "	"	" "	"	" "	"	" "	"	HEATER RECESS TO HAVE METAL LATH AND PLASTER WALLS AND CEILINGS.	
29	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
30	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
31	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
32	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
33	PLAYROOM	" "	" "	" "	"	" "	"	" "	"	" "	"		
34	PAINT & CLAY ROOM	" "	" "	" "	"	" "	"	" "	"	" "	"	HEATER RECESSES TO HAVE METAL LATH AND PLASTER WALLS AND CEILINGS.	ASPHALT TILE INLAY CIRCLE WITH 14'-6" RADIUS.
35	ASSEMBLY ROOM	" "	" "	" "	"	" "	"	" "	"	" "	"		
36	WOODWORK ROOM	" "	" "	" "	"	" "	"	" "	"	" "	"		
37	LIBRARY	" "	" "	" "	"	" "	"	" "	"	" "	"		
38	CLOAK ROOM	" "	" "	" "	"	" "	"	" "	"	" "	"		
39	" "	" "	" "	" "	"	" "	"	" "	"	" "	"		
40	STORAGE ROOM	" "	" "	" "	"	" "	"	" "	"	" "	"		
41	BOYS TOILET	" "	TROWELED SMOOTH	CEMENT	COLORED	CEM. PLAS. TROW. SMOOTH-MET. LATH	"	H.W. PLASTER-MET. LATH	SAND FIN. PAINTED	" "	"		
42	GIRLS TOILET	" "	" "	"	"	" "	"	" "	"	" "	"		
43	STORAGE	" "	ASPHALT TILE	WOOD	PAINTED	NO.30 SAND FIN. PLAS.-ROCK LATH	"	FIBRE BOARD	NATUREAL FIN.	" "	"	HEATER RECESS TO HAVE METAL LATH AND PLASTER WALLS AND CEILINGS.	
44	CLASSROOM	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
45	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
46	" "	" "	" "	" "	"	" "	"	" "	"	" "	"	"	
47	VISUAL AID	" "	" "	" "	"	" "	"	" "	"	" "	"		
48	BOYS TOILET	" "	TROWELED SMOOTH	CEMENT	COLORED	CEM. PLAS. TROW SMOOTH-MET. LATH	"	H.W. PLASTER - MET. LATH	PAINTED	" "	"		
49	GIRLS TOILET	" "	" "	"	"	" "	"	" "	"	" "	"		
50	SUPPLY & BOOKS	" "	ASPHALT TILE	WOOD	PAINTED	NO.30 SAND FIN. PLAS.	"	NO.30. SAND FIN. PLAS.	"	" "	"		
51	KITCHEN	" "	ASPHALT TILE (GREASE PROOF)	"	"	H.W. PLAS. TROW. SMOOTH	"	H.W. PLAS. TROW. SMOOTH.	"	" "	"		
52	DELIVERY	" "	ASPHALT TILE	"	"	" "	"	" "	"	" "	"		
53	TOILET	" "	" "	"	"	H.W. PLAS. SAND FIN.	"	PLAS. SAND. FINISH.	"	" "	"		
54	STORAGE	" "	" "	" "	"	" "	"	" "	"	" "	"		
55	EXIT CORRIDOR	" "	" "	" "	"	" "	"	" "	"	" "	"		
55-A	CHAIR STORAGE	" "	" "	" "	"	" "	"	" "	"	" "	"		
56	SERVING ISLE	" "	ASPHALT TILE (GREASE PROOF)	" "	"	H.W. PLAS. TROW. SMOOTH.	"	H.W. PLAS. TROW SMOOTH	"	" "	"		
57	STORAGE	1x4 OREGON PINE T&G	SAND & OIL	" "	"	H.W. PLAS. SAND. FIN.	"	H.W. PLAS. SAND FINISH	"	" "	"		
58	TOILET	" "	ASPHALT TILE	" "	"	" "	"	" "	"	" "	"		
59	STAGE	" "	SAND & OIL	" "	"	" "	"	" "	"	" "	"		
60	TOILET	" "	ASPHALT TILE	" "	"	" "	"	" "	"	" "	"		
61	DRESSING ROOM	" "	SAND & OIL	" "	"	" "	"	" "	"	" "	"		
62	" "	" "	" "	" "	"	" "	"	" "	"	" "	"		
63	ASSEMB. & CAFETERIA	4"CONC. SLAB	ASPHALT TILE	" "	"	NO 30. SAND. FIN. PLAS.	"	ACOUST. PLAS. ON H.W. PLAS.	NATURAL FIN.	" "	"	HEATER CLOSET TO HAVE METAL LATH AND PLASTER WALLS AND CEILINGS.	
64	ENTRY	" "	" "	" "	"	ROCK LATH	"	FIBRE BOARD	"	" "	"		
65	GENERAL OFFICE	" "	" "	" "	"	" "	"	" "	"	" "	"		
66	STORAGE	" "	" "	" "	"	" "	"	" "	"	" "	"		
67	PRINCIPAL	" "	" "	" "	"	" "	"	" "	"	" "	"		
68	TOILET	" "	" "	" "	"	" "	"	" "	"	" "	"		
69	TOILET	" "	" "	" "	"	" "	"	" "	"	" "	"		
69-A	SHOWER RM.	" "	CERAMIC TILE	6" CERAMIC TILE	COLOR SELECTED	CEM. PLAS. TROW. SMOOTH-MET. LATH	"	CEM. PLAS. TROW SMOOTH-MET. LATH	PAINTED	—	—	INCLUDES SHOWER	COLOR OF TILE ON FLOOR TO BE SELECTED.
70	VESTIBULE	" "	ASPHALT TILE	SOFT PINE	PAINTED	NO 30 SAND. FIN. PLAS.-ROCK LATH	"	FIBRE BOARD	NATURAL FIN.	WOOD- SOFT PINE	PAINTED		
71	HEALTH ROOM	" "	" "	" "	"	" "	"	" "	"	" "	"		
72	ARCADES	—	—	—	—	—	—	CEM. PLASTER MET. LATH	SAND FLOAT FIN.	—	—		

NOTE : ALTERNATE BYD PERTAINING TO WALLS ONLY.

ROOMS LISTED BELOW TO HAVE ALTERNATE BIDS FOR WALLS ONLY!

SEE REMARKS FOR ROOM NOS	ALL CLASSROOMS	4" conc. Slab	Asphalt Tile	wood	painted	Wherever plast. is used	Painted	Fibre board	Natural finish	Soft Pine	Painted	Metal lath & plaster @ partitions & ceilings of heater recesses in rooms	NOS 1 THRU 5 & 7, 10 THRU 20 & 28, 29 THRU 32, 44 THRU 47
" " "	KINDERGARTEN UNIT	"	"	"	"	"	"	"	"	"	"	BOYS & GIRLS TOILET ROOMS	NOS 34 THRU 40 & 42
" " "	ADMINISTRATION UNIT	"	"	"	"	"	"	"	"	"	"	TOILET ROOMS NOS 68, 69 & 69-A	NOS 64 THRU 67, 70 & 71

Check and verify all dimensions before proceeding with the work. Report any discrepancies to Architect.

STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF ARCHITECTURE

BAKERSFIELD CITY SCHOOL
1300 EAST BAKERSFIELD CALIF.
BOARD OF EDUCATION

ELEMENTARY SCHOOL
BAKERSFIELD CITY SCHOOL DISTRICT
WAYSIDE & 34th STREETS
BAKERSFIELD, CALIFORNIA