℄ OF "A" STREET
CITY SEWER.
FL. 87.84' APPROX. LOCATION.
93'-0"
EXISTING CHAIN LINK FENCE
EXISTING WATER METERS
NOT TO SCALE
PAIR 6'-0" GATES
APPROX 254'-0"
1 SET 3 HIGH 20' NEW SWING SET
LOCATE EXISTING SWING SETS HERE
NEW 8'-0" CHAIN LINK FENCE
1 SET 3 LOW
NEW 20' SWING SET
NEW J.G.
FIRE HYDT.
NEW 8'-0" CHAIN LINK FENCE
SAND BOX
7'-0" NEW CONC. WALK
NEW 6'-0" CONCRETE WALK
FINISH FLOOR ELEV. 98'-6"
UNIT "D"
DO NOT MOVE UNLESS NECESSARY
108'-0"
167'-6"
LOCATION OF BUILDING THAT HAS BEEN REMOVED
REMOVE CONCRETE WALK
8'-0" CONCR. WALK
UNIT "C"
UNIT "B"
UNIT "A"
192'-5½"
EXISTING 6' CONC WALK
NOTE: REPLACE IN SECTIONS ANY DAMAGED EXISTING CONCR. WALKS. NO PATCHWORK ALLOWED.
NEW CONCR. WALK
CONC. CURB
EXISTING WATER WELL TO BE CAPPED WITH 4'-0" x 4'-0" x 6" CONCRETE PAD AT EL. 91.35'. THAN FILL WITH CLEAN SAND
REMOVE CONC. STEPS AND WALLS. FILL WITH CLEAN SAND AND TAMP.
REMOVE EXISTING PUMP HOUSE ALL CONC. WALLS, FLOOR AND FOOTING. FILL WITH CLEAN SAND AND TAMP.
REMOVE EXISTING CONCRETE SLAB
GAS METER 6x8 MECH.
610.50'
℄ OF SECOND STREET
F.F. EL. 100'-0"
1⅞" NEW SHEATHING & PLASTER
2" SEPARATION
APPLICATION Nº 312 MAY 15 1936
FINISH FLOOR ELEV. 100'-0"
APPLICATION Nº 2938 JUNE 17 1939
70' CONC. WALK
flag pole
6.6' CONC. WALK
UNIT "E"
FINISH FLOOR ELEV. 100'-0"
NEW 3'-0" x 5'-0" CONC. PAD AT EL. 98.75 FOR NEW MAIN SWITCH BOARD
DOWN
264.0'
6' CONC. WALK
PROPERTY LINE
PROPERTY CORNER
BENCH MARK 97.90' "X" IN CURB RETURN EQUALS 87.15' CITY DATUM.
℄ OF HOLTBY ROAD
LEGAL DESCRIPTION. THIS PARCEL SHOWN PARCEL-1. PARCEL-1- LOT 1 TO 24 INCLUSIVE IN BLOCK 4 AND LOTS 7 TO 12 INCLUSIVE IN BLOCK 2, OF GOODE TRACT IN THE CITY OF BAKERSFIELD, COUNTY OF KERN, STATE OF CALIFORNIA, AS PER MAP RECORDED MAY 23, 1910 IN BOOK 1, PAGE 144 OF MAPS IN THE OFFICE OF THE COUNTY RECORDER OF SAID COUNTY
NORTH
SCALE 1/16" = 1'-0"
FIN. GRADE
EXIST. GRADE
TREES TO REMAIN
TREES TO BE REMOVED
NEW CONSTRUCTION
NEW CONCRETE WORK
EXISTING BUILDINGS
SHEET INDEX
SHEET ARCHITECTURAL
A-1 PLOT PLAN
A-2 FLOOR PLAN
A-3 FLR. PLANS & ELEVATIONS
A-4 EXTERIOR ELEVATIONS
A-5 EXTERIOR ELEV'S. & DETAILS
A-6 ROOF PLAN & DETAILS
A-7 TYPICAL CLASSRM. & DETAILS
A-8 ¼" SCALE KITCHEN FLR. PLAN & INTERIOR ELEVATIONS
SHEET ARCHITECTURAL
A-9 INTERIOR ELEVATIONS
A-10 MISC. DETAILS
A-11 DOOR & WINDOW DETAILS
A-12 DOOR & SASH SCHEDULE & DETAILS
A-13 RM. FINISH SCHEDULE & MISC. DETAILS
STRUCTURAL
S-1 GEN. NOTES & TYP. DETAILS
S-2 FOUNDATION PLANS-UNITS "A", "B" & "C"
SHEET STRUCTURAL
S-3 ROOF FRAMING PLANS-UNITS "A", "B" & "C"
S-4 FOUNDATION & ROOF FRAMING PLAN UNITS "D" & "E"
S-5 TYP. CLSRM. SECTIONS-DETAILS
S-6 SHELTER SECTIONS & DETAILS
S-7 SECTIONS & DETAILS-UNIT "E"
S-8 MISC. SECTIONS & DETAILS
S-9 UNIT "E" SECTIONS & ST. JOIST DTLS
SHEET MECHANICAL
M-1 PLUMBING
M-2 PLUMBING
M-3 PLUMBING
M-4 HEATING & VENTILATING
M-5 HEATING & VENTILATING
E-1 PLOT PLAN & FLOOR PLANS
E-2 FLOOR PLANS
OFFICE OF SUPERINTENDENT OF SCHOOLS
APPROVED
DATE 11-16-53
STATE OF CALIFORNIA
DEPARTMENT OF PUBLIC WORKS
DIVISION OF ARCHITECTURE
STATE OF CALIFORNIA—DEPARTMENT OF PUBLIC WORKS DIVISION OF ARCHITECTURE
APPLICATION NO. 11362
APPROVED NOV 12 1953
SUPERVISING STRUCTURAL ENGINEER
CHECK AND VERIFY ALL DIMENSIONS AND CONDITIONS AT JOB SITE BEFORE PROCEEDING WITH THE WORK. REPORT ANY DISCREPANCIES TO THE ARCHITECT.
PLOT PLAN
℄ OF VERDE STREET
SCALE 1/16" = 1'-0"
BAKERSFIELD CITY SCHOOLS
1600 "K" ST. BAKERSFIELD CALIFORNIA
BOARD OF EDUCATION
APPROVED
DATE NOV 12 1953
ROOSEVELT ELEM. SCHOOL ADDITION
BAKERSFIELD CITY SCHOOL DISTRICT
2324 VERDE STREET
BAKERSFIELD CALIFORNIA
ERNEST L. McCOY A.I.A. ARCHITECT
2811 H STREET BAKERSFIELD
PHONE 4-9851 CALIFORNIA
C-338
JOB NO. 53-22
DATE 11-10-53
DRAWN
CHECKED
SHEET NO. A-1
OF 18 SHEETS